

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ROADWAY 90% FED 10% STATE URBAN	0005 ROADWAY 90% FED 10% STATE RURAL	0014 BRIDGE 90% FED 10% STATE RURAL	0005 OVERHEAD LTG 100% STATE URBAN			0005 ROADWAY 100% STATE RURAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	150	150						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	474	474						
20100500	TREE REMOVAL, ACRES	ACRE	1	0.6	0.4					
20200100	EARTH EXCAVATION	CU YD	3275	3275						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2538.3	1625	913.3					
20400800	FURNISHED EXCAVATION	CU YD	7195	7195						
20800150	TRENCH BACKFILL	CU YD	8.2	8.2						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7719	4801	2918					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	16109	16109						
21400100	GRADING AND SHAPING DITCHES	FOOT	4205	2195	2010					
* 25000210	SEEDING, CLASS 2A	ACRE	6.4	5	1.4					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	580	454.7	125.3					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	580	454.7	125.3					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	580	454.7	125.3					
* 25100115	MULCH, METHOD 2	ACRE	6.4	5	1.4					
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	688	688						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	8379	6568	1811					
28000305	TEMPORARY DITCH CHECKS	FOOT	810	810						
28000400	PERIMETER EROSION BARRIER	FOOT	346	346						
28000500	INLET AND PIPE PROTECTION	EACH	3	3						
28000510	INLET FILTERS	EACH	3	3						
28100107	STONE RIPRAP, CLASS A4	SQ YD	208	208						
28100125	STONE RIPRAP, CLASS B3	SQ YD	1054	1054						
28200200	FILTER FABRIC	SQ YD	1261	1261						
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	11564	8647	2917					

*SPECIALTY ITEMS

FILE NAME
D:\68506-aht-cover.dgn

USER NAME = ghidnaem	DESIGNED -	REVISED -
PLOT SCALE = 100.0000 ' / IN.	DRAWN -	REVISED -
PLOT DATE = 1/7/2011	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(48-27R,RS-4	KNOX	103	4
FED. ROAD DIST. NO. (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 68506	