

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | | | |
|-----------------------|--|-------|------------------------|--------------------------------------|--------------------------------------|-------------------------------------|------------------------------------|--|--|-------------------------------|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 0005 ROADWAY 90% FED 10% STATE URBAN | 0005 ROADWAY 90% FED 10% STATE RURAL | 0014 BRIDGE 90% FED 10% STATE RURAL | 0005 OVERHEAD LTG 100% STATE URBAN | | | 0005 ROADWAY 100% STATE RURAL |
| 31101900 | SUB BASE GRANULAR MATERIAL, TYPE C | TON | 2176.2 | 984.3 | 1191.9 | | | | | |
| 35300700 | PORTLAND CEMENT CONCRETE BASE COURSE 12" | SQ YD | 4776 | 2962 | 1814 | | | | | |
| 40600215 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | TON | 112.2 | 44.6 | 67.6 | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 1 | 1 | | | | | |
| 40600982 | HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 9923 | 5176 | 4747 | | | | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 3262 | 1675 | 1587 | | | | | |
| 40603310 | HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 12207.7 | 4377.9 | 7829.8 | | | | | |
| 40603535 | POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 131.9 | | | 131.9 | | | | |
| 40603545 | POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 10677.7 | 3816.2 | 6861.5 | | | | | |
| 40701946 | HOT - MIX ASPHALT PAVEMENT (FULL DEPTH), 13 1/4" | SQ YD | 3617 | 3617 | | | | | | |
| 42001200 | PAVEMENT FABRIC | SQ YD | 4776 | 2962 | 1814 | | | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 7730 | 5910 | 1820 | | | | | |
| 44000155 | HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 111712 | 38482 | 73230 | | | | | |
| 44000161 | HOT - MIX ASPHALT SURFACE REMOVAL, 3" | SQ YD | 763 | | 763 | | | | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 146 | 146 | | | | | | |
| 44004000 | PAVED DITCH REMOVAL | FOOT | 706 | 706 | | | | | | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 8124 | 5386 | 2738 | | | | | |
| 44201297 | DOWEL BARS 1 " | EACH | 144 | 48 | 96 | | | | | |
| 44213204 | TIE BARS 3/4" | EACH | 700 | 435 | 265 | | | | | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 5565.3 | 2036.3 | 3529 | | | | | |
| 48203029 | HOT - MIX ASPHALT SHOULDERS, 8" | SQ YD | 3944 | 2928 | 1016 | | | | | |
| 48203039 | HOT - MIX ASPHALT SHOULDERS, 10 1/2" | SQ YD | 3086 | 1816 | 1270 | | | | | |
| 50104400 | CONCRETE HEADWALL REMOVAL | EACH | 1 | 1 | | | | | | |
| 50104650 | SLOPE WALL REMOVAL | SQ YD | 679 | 679 | | | | | | |

*SPECIALTY ITEMS

| | | | |
|-------------------------------------|-------------------------------|------------|-----------|
| FILE NAME D:\68506-shr-cover.dgn | USER NAME = ghdmn | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 1/7/2011 | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| | | | | |
|---|---------------|--------|--------------------|-----------|
| F.A.J. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 74 | (48-27)R,RS-4 | KNOX | 103 | 5 |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 68506 | |