

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ROADWAY 90% FED 10% STATE URBAN	0005 ROADWAY 90% FED 10% STATE RURAL		0014 BRIDGE 90% FED 10% STATE RURAL	0005 OVERHEAD LTG 100% STATE URBAN			0005 ROADWAY 100% STATE RURAL
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	165					165			
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	2579	1408	1171						
Z0004556	HOT - MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1383				1383				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.4	0.6						
* Z0016702	DETOUR SIGNING	L SUM	1	0.4	0.6						
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2						
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2						
Z0034105	MATERIAL TRANSFER DEVICE	TON	31101	11041	20060						
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	8014	5586	2428						
40603216	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL - 12.5, N90	TON	15034	5289	9745						

*SPECIALTY ITEMS

FILE NAME 0468506-shr-cover.dgn	USER NAME = ghdsrnm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/7/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	48-27R,RS-4	KNOX	103	9
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68506	