LOCATION	ENGINEER'S FIELD OFFICE, TYPE A	ENGINEER'S FIELD LABORATORY	MOBILIZATION	CHANGEABLE MESSAGE SIGN	CONSTRUCTION LAYOUT	DETOUR SIGNING
	CAL. MO.	CAL. MO.	L. SUM	CAL. MO.	L. SUM	L. SUM
JOBSITE	8	8	1	16	1	1
URBAN TOTAL	**8**	**8**	**0.4**	**5**	**0.4**	**0.4**
RURAL TOTAL			**0.6**	**11**	**0.6**	**0.6**

ITEM DESCRIPTION	UNIT	TOTAL QTY.
UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE),1" DIA. POLYETHYLENE	FOOT	232
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6 FOOT EC C XLP USE 1C 6	FOOT	330
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	232
BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	8
RELOCATE EXISTING LIGHTING UNIT	EACH	2
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	1
ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	165

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	EACH	EACH
SN 048-0058				
EB CLOSE DRIVE LANE	850		1	
WB CLOSE DRIVE LANE	850		1	
EB CLOSE PASS LANE		850		1
WB CLOSE PASS LANE		850		1
SN048-0048				
EB CLOSE DRIVE LANE	937.5		1	
WB CLOSE DRIVE LANE	537.5		1	
EB CLOSE PASS LANE		937.5		1
WB CLOSE PASS LANE		537.5		1
URBAN TOTAL	**1700**	**1700**	**2**	**2**
RURAL TOTAL	**1475**	**1475**	**2**	**2**

LOCATION	MOWING	DELINEATORS
	UNIT	EACH
JOBSITE		
STA. 327+05 TO 519+24	192	
MAIN ST.		
RAMP A	12	12
RAMP C	8	8
RAMP D	10	12
RAMP E	5	5
RAMP H	9	9
CH 9		
RAMP A	14	13
RAMP B	12	10
RAMP C	16	14
RAMP D	11	10
URBAN TOTAL	**112**	**46**
RURAL TOTAL	**177**	**47**

LOCATION	TRAFFIC CONTROL AND PROTECTION							
	STANDARD 701401	STANDARD 701402	STANDARD 701411	STANDARD 701451	STANDARD 701456	STANDARD 701601	STANDARD 701406	TRAFFIC CONTROL SURVEILLANCE
	EACH	EACH	EACH	LSUM	LSUM	LSUM	LSUM	CAL DAY
ENTIRE JOBSITE	2	2	8	1	1	1	1	100
URBAN TOTAL	**1**	**0.7**	**4**	**0.4**	**0.4**	**0.4**	**0.4**	**35.3**
RURAL TOTAL	**1**	**1.3**	**4**	**0.6**	**0.6**	**0.6**	**0.6**	**64.7**