



LT. STA. 1+23 TO STA. 1+37 (EX. RAMP H)
CCC&G REMOVAL = 26.6 FT.

RT. STA. 33+51 (EX. MAIN ST.)
OFFSET = 33.08 FT.

RT. STA. 32+36 (EX. MAIN ST.)
OFFSET = 32.96 FT.

RT. STA. 31+71 TO STA. 32+77 (EX. MAIN ST.)
CCC&G REMOVAL = 119.2 FT.

RT. STA. 31+95 (EX. MAIN ST.)
OFFSET = 45.06 FT.

STA. 1+03 TO STA. 16+74 (EX. RAMP H)
PAVEMENT REMOVAL = 2933.5 SQ. YD.

RT. STA. 0+89 (EX. RAMP H) TO STA. 367+31 (EX. I-74)
PAVED SHOULDER REMOVAL = 2031.6 SQ. YD.

LT. STA. 1+37 TO STA. 8+45 (EX. RAMP H)
PAVED SHOULDER REMOVAL = 616.3 SQ. YD.
INCLUDES SHOULDER REMOVAL ALONG I-74
FROM STA. 353+00 TO 355+27 AND THE GORE AREA.

LT. STA. 1+37 TO STA. 8+45 (EX. RAMP H)
PIPE UNDERDRAINS, REMOVAL = 708.0 FT.

RT. STA. 0+89 (EX. RAMP H) TO STA. 367+31 (EX. I-74)
PIPE UNDERDRAINS, REMOVAL = 1,974.0 FT.

SEE SCHEDULES FOR TREE REMOVAL QUANTITIES AND LOCATIONS.



FILE NAME =
D466506-shr-prof1a.dgn

USER NAME = bergsekere

DESIGNED -

REVISED -

DRAWN -

REVISED -

CHECKED -

REVISED -

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

REMOVAL SHEET
RAMP H

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(48-27)R,RS-4	KNOX	103	30
			CONTRACT NO. 68506	
ILLINOIS FED. AID PROJECT				