

SCHEDULE OF QUANTITIES

EPOXY PVMT. MRKG.-LINE 4"

LOCATION	FOOT
Jobsite - SN.072-0134	1000
TOTAL	1000

EPOXY PVMT. MRKG.-LINE 6"

LOCATION	FOOT
Jobsite - SN.072-0134	320
TOTAL	320

EPOXY PVMT. MRKG.-LINE 12"

LOCATION	FOOT
Median Intro @ I-474 Exit Ramp	50
TOTAL	50

PVMT. MRKG. REMOVAL

LOCATION	SQFT
Jobsite - SN.072-0134	500
TOTAL	500

CONCRETE MEDIAN REMOVAL

LOCATION	SQFT
Jobsite - SN.072-0134	290
TOTAL	290

PARAPET RAILING, SPECIAL

LOCATION	FOOT
North Parapet	40
TOTAL	40

TRAFFIC CONTROL & PROT. SPECIAL

LOCATION	LSUM
Jobsite - SN.072-0134	1
TOTAL	1

WIDTH RESTRICTION SIGNING

LOCATION	LSUM
Jobsite - SN.072-0134	1
TOTAL	1

JACK & REMOVE EXIST. BRGS.

LOCATION	EACH
East Joint	19
TOTAL	19

STRUCT. REP. OF CONC. =< 5" DEPTH

LOCATION	SQFT
East Abutment	110.25
TOTAL	110.25

STRUCT. REP. OF CONC. > 5" DEPTH

LOCATION	SQFT
East Abutment	19.5
TOTAL	19.5

IMPACT ATTENUATORS, TEMP. (NRD, TEST LEVEL 2)

LOCATION	EACH
Jobsite - SN.072-0134	3
TOTAL	3

IMPACT ATTENUATORS, RELOCATE (NRD, TEST LEVEL 2)

LOCATION	EACH
Jobsite - SN.072-0134	3
TOTAL	3

S:\GEN\DRIFT\STDBPLNS\SQUAD BRIDGES\BRIDGE CONTRACTS\JOINTS\66995 SN072-0134\SN072-0134 US24ovrKicpooCrk.dgn

FILE NAME = SN072-0134 US24ovrKicpooCrk.dgn	USER NAME = jonesc	DESIGNED - C JONES	REVISED - -----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES STRUCTURE NO. 072-0134	F.A.P. RTE. 317	SECTION (48B)1-1	COUNTY PEORIA	TOTAL SHEETS 26	SHEET NO. 7	
PLOT SCALE = 183.7051' / IN.	CHECKED - ----	REVISOR - C JONES	REVISOR - -----			N.Abut. Rehab. Brgs./Jt. Repl.	CONTRACT NO. 68995		ILLINOIS FED. AID PROJECT		
PLOT DATE = 1/10/2011	DATE - 12/28/2010	REVISOR - -----	REVISOR - -----			SCALE: -----	SHEET NO. -- OF -- SHEETS	STA. ----- TO STA. -----			