SCHEDULES OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING, LINE 8"

STA.	TO	STA.	LOCATION	COLOR	LENGTH (FT)	NUMBER OF STRIPES	THERMOPLASTIC PAVEMENT MARKING, LINE 8" 78000500 (FT)
1079+25		1082+00	RAMP AC	WHITE	275	2	550
1075+74		1079+65	RAMP CB	WHITE	391	2	782
1100+42		1103+42	RAMP DA	WHITE	300	2	600
1099+80		1102+60	RAMP BD	WHITE	280	2	560
						TOTAL =	2492
						ROUND TO:	2500

THERMOPLASTIC PAVEMENT MARKING, LINE 12"

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING, LINE 12" 78000600 (SQ FT)
EB OFF RAMP	CB ISLAND	148
WB OFF RAMP	DA ISLAND	89
	TOTAL =	237
	ROUND TO:	250

THERMOPLASTIC PAVEMENT MARKING, LINE 24"

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING, LINE 24" 78000650 (SQ FT)
EB OFF RAMP	CB RT. TURN	18
EB OFF RAMP	CB LT. TURN	16
WB OFF RAMP	DA RT. TURN	18
WB OFF RAMP	DA LT. TURN	20
	TOTAL =	72
	ROUND TO:	75

CHANGEABLE MESSAGE SIGN

CHANGEABLE MESSAGE SIGN X7015005 LOCATION	14 DAYS BEFORE CONSTRUCTION OPPERATIONS BEGIN (STAGE 1) (CAL DAY)	7 DAYS BEFORE RAMP CLOSURES (CAL DAY)	DURING RAMP CLOSURES (CAL DAY)
I-74 EAST OF THE JOB (WB LANES)	14		
I-74 WEST OF THE JOB (EB LANES)	14		
I-74 EAST OF LEROY (WB LANES)		7	4
I-74 BETWEEN LEROY & DOWNS (WB)		7	
I-74 WEST OF US 51 (EB LANES)		7	4
I-74 BETWEEN US 51 AND DOWNS (EB)		7	
US 150 EAST OF TOWANDA-BARNES ROAD / US 150 INTERSECTION (EB)		7	4
US 150 EAST OF DOWNS (WB)		7	4
US 51 SOUTH OF VETERAN'S PKWY (SB)			4
US 51 SOUTH OF I-74 (NB)			4
TOTALS =	28	42	24

GRAND TOTAL = 94 CAL DAYS

SHEET REVISED 2-23-11

FILE NAME = c:\pw_work\pwidot\piersonbr\d0158340\D570550-sht-schedule.dgn	USER NAME = piersonbr	DESIGNED -	REVISED - Addendum #1 2/11	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN -	REVISED -	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
	PLOT DATE = 2/18/2011	DATE -	REVISED -	

SCHEDULES OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(57-20(1),21,22)RS-3	MCLEAN	150	50

CONTRACT NO. 70550

ILLINOIS FED. AID PROJECT