

* THICKNESS SHOWN FOR INFORMATION ONLY.

SCHEDULES OF QUANTITIES

HOT-MIX ASPHALT AND HOT-MIX ASPHALT SURFACE REMOVAL (SHEET 1 OF 8)

WESTBOUND DRIVING LANE

LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	POLYMERIZED HMA BINDER COURSE, IL19.0, FG, N105 40603244 (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N105 40603550 (TON)	HMA SURFACE REMOVAL, 4 1/2" 44000167 (SQ YD)	HMA SURFACE REMOVAL, 5" 44000169 (SQ YD)	HMA SURFACE REMOVAL, 5 1/2" 44000171 (SQ YD)	POLYMERIZED HMA BINDER COURSE, N105 40603245 (TON)
WBDL BIND	737+00.		737+52.5	52.5	12.5	72.9	4.13	0	7.3	0.15	16.86			72.9		
WBDL BIND	737+52.5		771+92.5	3,440.0	12.5	4,777.8	5	0	477.8	9.56	1337.78			4777.8		
WBDL BIND	771+92.5		772+07.5	15.0	12.5	20.8	4.75	0	2.1	0.04	5.54		10.4	10.4		
WBDL BIND	772+07.5		778+85.97	678.5	12.5	942.3	4.5	0	94.2	1.88	237.46		942.3			
WBDL BIND	778+85.97		779+38.47	52.5	12.5	72.9	3.63	0	7.3	0.15	14.82		72.9			
WBDL SURF	737+00.		779+38.47	4,238.5	12.0	5,651.3	0	1.75				553.83				
OMMISION S.N. 057-0121	WBDL		779+38.47	781+58.39	219.9											
	WBDL		781+58.39	782+10.89	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		782+10.89	828+59.25	4,648.4	12.0	6,197.8	5.5	1.75	619.8	12.40	1908.93			6,197.8	
OMMISION PCC PATCH	WBDL		828+59.25	829+11.75	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		829+11.75	837+66.33	854.6											
	WBDL		837+66.33	838+18.83	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		838+18.83	905+67.5	6,748.7	12.0	8,998.2	5.5	1.75	899.8	18.00	2771.45			8,998.2	
TRANS UNDER S.N. 057-0123	WBDL		905+67.5	906+20.	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
TRANS UNDER S.N. 057-0123	WBDL		906+20.	909+25.	305.0	12.0	406.7	3.75	1.75	40.7	0.81	85.40			406.7	
TRANS UNDER S.N. 057-0123	WBDL		909+25.	909+77.5	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		909+77.5	1005+74.5	9,597.0	12.0	12,796.0	5.5	1.75	1,279.6	25.59	3941.17			12,796.0	
TRANS UNDER S.N. 057-0124	WBDL		1005+74.5	1006+27.	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
TRANS UNDER S.N. 057-0124	WBDL		1006+27.	1009+32.	305.0	12.0	406.7	3.75	1.75	40.7	0.81	85.40			406.7	
TRANS UNDER S.N. 057-0124	WBDL		1009+32.	1009+84.5	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		1009+84.5	1037+21.75	2,737.3	12.0	3,649.7	5.5	1.75	365.0	7.30	1124.10			3,649.7	
OMMISION S.N. 057-0126	WBDL		1037+21.75	1037+74.25	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	
	WBDL		1037+74.25	1040+25.75	251.5											
	WBDL		1040+25.75	1040+78.25	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	18.15
	WBDL		1040+78.25	1088+30.	4,751.8	12.0	6,335.7	5.5	1.75	633.6	12.67	620.90			6,335.7	1951.39
TRANS UNDER S.N. 057-0127	WBDL		1088+30.	1088+82.5	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	18.15
TRANS UNDER S.N. 057-0127	WBDL		1088+82.5	1091+97.5	315.0	12.0	420.0	3.75	1.75	42.0	0.84	41.16			420.0	88.20
TRANS UNDER S.N. 057-0127	WBDL		1091+97.5	1092+50.	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	18.15
	WBDL		1092+50.	1110+47.5	1,797.5	12.0	2,396.7	5.5	1.75	239.7	4.79	234.87			2,396.7	738.17
	WBDL		1110+47.5	1111+00.	52.5	70.0	4.63	1.75	7.0	0.14	18.15	6.86			70.0	18.15
WBDL TOTALS =									4,833.4	96.7	11,674.1	4,713.7	1,025.6	4,861.1	42,447.4	2,850.4

FILE NAME =	USER NAME = hogenbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvt\work\pvt\dot\hogenbj\0158340\0570127	057-sht-schedule.dgn	DRAWN -	REVISED -			74	(57-201),21,22RS-3	MCLEAN	150	34
	PLOT SCALE = 1/8" = 1' IN.	CHECKED -	REVISED -							
	PLOT DATE = 10/28/2010	DATE -	REVISED -							
						SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT	
						CONTRACT NO. 70550				