

\* THICKNESS SHOWN FOR INFORMATION ONLY.

## SCHEDULES OF QUANTITIES

### HOT-MIX ASPHALT AND HOT-MIX ASPHALT SURFACE REMOVAL (SHEET 4 OF 8)

#### MAINLINE RAMPS

	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	* BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	POLYMERIZED HMA BINDER COURSE, IL19.0, FG, N105 40603244 (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N105 40603550 (TON)	HMA SURFACE REMOVAL, 5" 44000169 (SQ YD)	HMA SURFACE REMOVAL, 5 3/4" 44000172 (SQ YD)
WESTBOUND OFF	RAMP DA	10+00.		27+60.49	1,760.5	16 +/-	3,369.7	5	1.75	337.0	6.74	943.52	330.23	3,369.7	
EASTBOUND OFF	RAMP CB	10+00.		28+63.98	1,864.0	16 +/-	3,139.6	5	1.75	314.0	6.28	879.09	307.68	3,139.6	
WESTBOUND ON	RAMP AC	10+24.		31+64.13	2,140.1	16 +/-	3,174.3	5.75	1.75	317.4	6.35	1022.12	311.08		3,174.3
EASTBOUND ON	RAMP BD	10+24.		32+79.31	2,255.3	16 +/-	3,392.6	5.75	1.75	339.3	6.79	1092.42	332.47		3,392.6
RAMP TOTALS =										1,307.6	26.2	3,937.1	1,281.5	6,509.3	6,566.9

#### RAMP SHOULDERS

	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	* BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	HOT-MIX ASPHALT SHOULDERS 48203100 (TON)
WESTBOUND OFF	RAMP DA SHLD	10+00.		27+60.49	1,760.5	12' +/-	2,110.9	0	1.75	211.1	4.22	206.9
EASTBOUND OFF	RAMP CB SHLD	10+00.		28+63.98	1,864.0	12' +/-	2,248.9	0	1.75	224.9	4.50	220.4
WESTBOUND ON	RAMP AC SHLD	10+24.		31+64.13	2,140.1	12' +/-	2,431.7	0	1.75	243.2	4.86	238.3
EASTBOUND ON	RAMP BD SHLD	10+24.		32+79.31	2,255.3	12' +/-	2,584.9	0	1.75	258.5	5.17	253.3
RAMP SHLD TOTALS =										937.6	18.8	918.9

#### MAINLINE COUNTY HIGHWAY 36

	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	* BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	POLYMERIZED HMA SURFACE COURSE, MIX "C", N50 40603310 (TON)	HMA SURFACE REMOVAL, 1 1/2" 44000155 (SQ YD)
	CH 36	16+92.44		69+50.	5,257.6	VAR	15,505.3	0	1.5	1,550.5	31.01	1302.45	15,505.3

#### COUNTY HIGHWAY 36 SHOULDERS

	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	* BINDER THICKNESS (IN)	SURFACE THICKNESS (IN)	BIT. MATLS (PRIME COAT) 40600100 (GALLONS)	AGGREGATE (PRIME COAT) 40600300 (TON)	HMA SURFACE REMOVAL, 1 1/2" 44000155 (SQ YD)	HOT-MIX ASPHALT SHOULDERS 48203100 (TON)
	CH 36 SHLD	16+92.44		69+50.	5,257.6	20' +/-	11,149.9	0	1.5	1,115.0	22.30	11149.9	936.6