

SCHEDULES OF QUANTITIES

POLYUREA PAVEMENT MARKING

STA.	TO	STA.	DIRECTION	LENGTH (FT)	NUMBER OF STRIPES	EDGE LINE LENGTH (FT)	SKIP DASH LENGTH (FT)	SKIP DASH NEAREST 10' (FT)	POLYUREA PAVEMENT MARKING, TYPE 2, LINE 4" 78008310 (FT)
779+38.47		781+58.39	WB	219.9	2	439.8	55.0	60	499.8
779+38.47		781+58.39	EB	219.9	2	439.8	55.0	60	499.8
1037+74.25		1040+25.75	WB	251.5	2	503.0	62.9	70	573.0
1037+74.25		1040+25.25	EB	251.0	2	502.0	62.8	70	572.0
829+11.75		837+66.33	WB	854.6	2	1,709.2	213.6	220	1,929.2
TOTAL =									4,073.8
ROUND TO:									4,100

YELLOW = $[4100' - (60' + 60' + 70' + 70' + 220')] / 2 = 1810'$
 WHITE = $4100' - 1810' = 2290'$

PREFORMED PLASTIC PAVEMENT MARKING

STA.	TO	TO STA.	DIRECTION	LENGTH (FT)	SKIP DASH LENGTH (FT)	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LINE 4" 78003110 (FT)
737+00		779+38.47	WB	4,238.5	1,059.6	1,060
737+00		779+38.47	EB	4,238.5	1,059.6	1,060
781+58.39		829+11.75	WB	4,753.4	1,188.3	1,190
837+66.33		1037+74.25	WB	20,007.9	5,002.0	5,010
1040+25.25		1111+00	EB	7,074.8	1,768.7	1,770
1040+25.75		1111+00	WB	7,074.3	1,768.6	1,770
TOTAL =						11,860
ROUND TO:						12,000

THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS

STA.	LOCATION	TYPE	AREA EACH (SQ FT)	NUMBER	THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS 78000100 (SQ FT)
44+70.9	SB CH 36	LEFT TURN	15.6	1	15.6
45+33.23	SB CH 36	LEFT TURN	15.6	1	15.6
45+95.56	SB CH 36	LEFT TURN	15.6	1	15.6
46+57.89	SB CH 36	LEFT TURN	15.6	1	15.6
53+35.27	SB CH 36	LEFT TURN	15.6	1	15.6
53+97.60	NB CH 36	LEFT TURN	15.6	1	15.6
54+59.93	NB CH 36	LEFT TURN	15.6	1	15.6
55+22.26	NB CH 36	LEFT TURN	15.6	1	15.6
TOTAL =					124.8
ROUND TO:					125