

LOCATION OF WORK:

CULVERT NO. 1

CULVERT NO. 2

STA. 172+31
RURAL
S.N. 092-8086
PROP PCBC
10 X 5
80% FED
20% STATE
0040

STA. 272+92
RURAL
S.N. 092-8087
PROP PCBC
7 X 5
80% FED
20% STATE
0040

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0	1.0	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0		1.0
51500100	NAME PLATES	EACH	2.0	1.0	1.0
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2.0	2.0	
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2.0		2.0
54011005	PRECAST CONCRETE BOX CULVERTS 10' X 5'	FOOT	85.0	85.0	
54020705	PRECAST CONCRETE BOX CULVERTS 7' X 5' (M273)	FOOT	40.0		40.0
* 63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FOOT 6 IN SPAN	FOOT	325.0		325.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4.0		4.0
63200310	GUARDRAIL REMOVAL	FOOT	400.0		400.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5.0	2.5	2.5
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0	0.5	0.5
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	50.0	20.0	30.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0		4.0
* X0323115	REFLECTOR MARKERS, TYPE A	EACH	8.0		8.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	20.0	10.0	10.0
Z0038700	PERMANENT BENCH MARKS	EACH	2.0	1.0	1.0
Z0037200	PAVEMENT GRINDING	SQ YD	235.0	125.0	110.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = sherer,jm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cc:\pwork\pwork\sherer,jm\d0189007\057617-sht-500.dgn		DRAWN - JMS	REVISED -		711	115CR	VERMILION	39	5				
PLOT SCALE = 100.0000 "/ IN.		CHECKED -	REVISED -		CONTRACT NO. 70617								
PLOT DATE = 11/16/2010		DATE - 031210	REVISED -		SCALE: N/A	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				