## EARTHWORK SCHEDULE

LANDSCAPI	ING SCHEDULE											
						28000250 TEMPORARY	25000350	25000200	25000400	25000500	25000600	25100115
						EROSION	SEEDING	SEEDING	NITROGEN	PHOS	POTAS.	MULCH
					AREA	SEEDING	CLASS 7	CLASS 2	FERT.	FERT.	FERT.	METHOD 2
	STATION	<u>TO</u> .		STATION	(ACRE)	(POUND)	(ACRE)	(ACRE)	(POUNDS)	(POUNDS)	(POUNDS)	(ACRE)
CULVERT N	IO. 1											
LT	171+29.83		LT	173+36.77	0.2	20.0	0.2	0.2	18.0	18.0	18.0	0.2
RT	171+28.69		RT	173+09.85	0.2	20.0	0.2	0.2	18.0	18.0	18.0	0.2
				SUB-TOTAL =	0.4	40.0	0.4	0.4	36.0	36.0	36.0	0.4
CULVERT N	10.2											
LT	270+72.44		LT	274+32.89	0.3	30.0	0.3	0.3	27.0	27.0	27.0	0.3
RT	270+47.13		RT	274+21.32	0.3	30.0	0.3	0.3	27.0	27.0	27.0	0.3
				SUB-TOTAL =	0.6	60.0	0.6	0.6	54.0	54.0	54.0	0.6
				TOTAL =	1.0	100.0	1.0	1.0	90.0	90.0	90.0	1.0

## SCHEDULE NOTE: IT IS THE INTENT THAT CLASS 7 SEEDING BE PLACED ALONG WITH THE CLASS 2 SEEDING AS A SUPPLEMENTAL SEEDING TO PROMOTE ACCELERATED VEGETATION GROWTH.

28000305 TEMPORARY DITCH CHECKS

	STATION		FOOT	28000400	28000400 PERIMETER EROSION BARRIER							
CULVERT NO. 1					STATION	10		STATION		FOOT		
LT	171+28.69		20.0	CULVERT	'NO. 1							
RT	171+23.12		20.0									
LT	173+14.10		20.0	RT	171+29.83		RT	173+36.77		212.0		
RT	173+43.89		20.0	LT	171+28.69		LT	173+09.85		185.0		
		SUB-TOTAL =	80.0						SUB-TOTAL =	397.0		
CULVERT NO. 2				CULVERT	NO.2							
LT	270+47.24		20.0	RT	270+72.44		RT	274+32.89		384.4		
RT	270+72.44		20.0	LT	270+47.13		LT	274+21.32		414.3		
LT	271+47.27		20.0									
RT	271+59.18		20.0						SUB-TOTAL =	799.0		
LT	272+38.22		20.0									
RT	272+58.67		20.0						TOTAL =	1196.0		
LT	273+21.13		20.0									
RT	274+01.27		20.0									
LT	274+21.25		20.0									
		SUB-TOTAL =	180.0									
	-	TOTAL =	260.0									

	STATION	ю		STATION	20200100 EARTH EXCAVATION <u>(CU YD)</u>	ADJUSTED FOR SHRINKAGE <u>(CU YD)</u>	EMBANKMENT (CU YD)	20400800 *FURNISHED EXCAVATION <u>(CU YD)</u>
	CULVERT NO.1							
LT/RT	171+00	L	.T/RT	173+50	50.0	38.0	64.0	-26.0
				SUB-TOTAL =	50.0	38.0	64.0	-26.0
	CULVERT NO. 2							
LT/RT	271+00	L	.T/RT	274+00	133.0	100.0	166.0	-66.0
				SUB-TOTAL =	133.0	100.0	166.0	-66.0
			_	TOTAL =	183.0	138.0	230.0	-92.0

\*FURNISHED EXCAVATION = EARTH EXCAVATION X ADJUSTMENT FACTOR (0.75) - EMBANKMENT

## 21301052 EXPLORATION TRENCH, 52"

	STATION	ю		STATION		<u>F00T</u>
CUL	/ERT NO. 1					
RT	171+33.00		RT	172+33.00		200.0
LT	171+33.00		LT	172+33.00		200.0
					SUB-TOTAL =	400.0
CUL	/ERT NO. 2					
RT	272+00.00		RT	273+65.09		165.0
LT	272+00.00		LT	273+65.09		165.0
					SUB-TOTAL =	330.0

<u>*28100107 s</u>	TONE RIPRAP, CLAS	<u>SS A4</u>		28200200 FILTER FABRIC
	STATION		<u>SQ YD</u>	<u>SQ YD</u>
	CULVERT NO. 1			
LT	172+33.00		76.0	76.0
RT	172+33.00		137.0	137.0
	-	TOTAL =	213.0	213.0

\* THE ENGINEER MAY MODIFY LOCATIONS OF

STONE RIPRAP, CLASS A4 BASED ON FIELD CONDITIONS

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -						F.A.P.	SECTION	COUNTY TOTAL SH
c:\pw_work\pwidot\shererjm\d018900	7\D57 <b>0</b> 617-sht-schedules.dgn	DRAWN - JMS	REVISED -	STATE OF ILLINOIS		SCHEDULE OF Q	JANTITIES		711	115CR	VERMILION 39
	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							CONTRACT NO. 706
	PLOT DATE = 11/22/2010	DATE - 031210	REVISED -		SCALE: N/A	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.		ILLINOIS FE	D. AID PROJECT