

# SUMMARY OF QUANTITIES

SHEET 1 OF 2

LOCATION OF WORK:	<b>L20</b> FAP 804	<b>L25</b> FAP 804	GRAHAM ST. & CHURCH ST.	CH 18 / (MONTICELLO RD.)
COUNTY:	MULTI-LANE URBAN CHAMPAIGN	MULTI-LANE RURAL CHAMPAIGN	2 LANE URBAN CHAMPAIGN	2 LANE URBAN CHAMPAIGN
FUNDING BREAKOUT:	STA. 135+00.00 TO STA. 297+00.00	STA. 297+00.00 TO STA. 415+00.00	100% VILLAGE OF SAVOY	100% CHAMPAIGN COUNTY
CONSTRUCTION TYPE CODE:	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE OF SAVOY	100% CHAMPAIGN COUNTY
	0005	0005	0005	0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
<b>44022063</b>	PARTIAL DEPTH REMOVAL 11 1/2"	SQ YD	103.0	89.0	14.0		
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6429.0	3380.0	3049.0		
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	16073.0	8450.0	7623.0		
40300600	SEAL COAT AGGREGATE	TON	482.0	253.0	229.0		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19197.0	10445.0	8752.0		
40600300	AGGREGATE (PRIME COAT)	TON	384.0	209.0	175.0		
40600895	CONSTRUCTING TEST STRIP	EACH	1.0		1.0		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	3350.0	270.0		900.0	2180.0
40600990	TEMPORARY RAMP	SQ YD	473.0	312.0	103.0	40.0	18.0
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	18813.0	10236.0	8577.0		
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	335.0	27.0		90.0	218.0
40800030	AGGREGATE (PRIME COAT)	TON	7.0	1.0		2.0	4.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	282.0	23.0		76.0	183.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 11/2"	SQ YD	191973.0	104453.0	87520.0		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7.0	5.0		2.0	
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	2.0			2.0	
64200105	SHOULDER RUMBLE STRIPS	FOOT	72100.0	34042.0	38058.0		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6.0	3.0	3.0		
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1.0	0.5	0.5		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0	1.0			

FILE NAME =	USER NAME = bucklesjj	DESIGNED - GAE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pwwork\pwwork\pwwork\bucklesjj\d0210355\0570708-sh1-500.dgn	DRAWN - BBP	CHECKED -	REVISED -			804	(23,24,25)RS-5	CHAMPAIGN	61	5	
PLOT SCALE = 40.0000 / IN.	DATE - 12/09/10	REVISOR -	REVISOR -			CONTRACT NO. 70708					
PLOT DATE = 12/16/2010						ILLINOIS FED. AID PROJECT					
				SCALE: NONE		SHEET NO. 1 OF 2 SHEETS		STA.		TO STA.	