

SCHEDULE OF QUANTITIES

SHEET 4 OF 14

BITUMINOUS SURFACE TREATMENT, CLASS A-1

(SHOULDER SEAL OPERATIONS)

						40300300	40300600	40300100	
						BITUMINOUS MATERIALS COVER & SEAL COATS (GALLON)	SEAL COAT AGGREGATE (TON)	BITUMINOUS MATERIALS PRIME COAT (GALLON)	
LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)			
S.B. RT.	135+00.00		145+36.60 (BK)	1036.60	9.00	1036.60	259.15	7.77	103.66
S.B. RT.	145+36.40 (AH)		156+70.00	1133.60	9.00	1133.60	283.40	8.50	113.36
S.B. RT.	157+50.00		176+20.00	1870.00	9.00	1870.00	467.50	14.03	187.00
S.B. RT.	201+20.00		206+70.00	550.00	3.00	183.33	45.83	1.38	18.33
S.B. RT.	207+70.00		211+70.00	400.00	3.00	133.33	33.33	1.00	13.33
S.B. RT.	213+30.00		236+08.00	2278.00	9.00	2278.00	569.50	17.09	227.80
S.B. RT.	236+08.00		238+77.00	269.00	7.00	209.22	52.31	1.57	20.92
S.B. RT.	238+77.00		241+74.00	297.00	4.00	132.00	33.00	0.99	13.20
S.B. RT.	242+28.00		242+72.00	44.00	4.00	19.56	4.89	0.15	1.96
S.B. RT.	243+00.00		257+42.49 (BK)	1442.49	9.00	1442.49	360.62	10.82	144.25
S.B. RT.	257+42.06 (AH)		289+56.00	3213.94	9.00	3213.94	803.49	24.10	321.39
S.B. RT.	289+56.00		292+26.00	270.00	7.00	210.00	52.50	1.58	21.00
S.B. RT.	292+26.00		294+80.00	254.00	4.00	112.89	28.22	0.85	11.29
S.B. RT.	297+22.00		343+07.00	4585.00	9.00	4585.00	1146.25	34.39	458.50
S.B. RT.	343+07.00		345+77.00	270.00	7.00	210.00	52.50	1.58	21.00
S.B. RT.	345+77.00		348+30.00	253.00	4.00	112.44	28.11	0.84	11.24
S.B. RT.	350+14.00		357+83.75 (BK)	769.75	9.00	769.75	192.44	5.77	76.98
S.B. RT.	357+83.17 (AH)		392+99.99 (BK)	3516.82	9.00	3516.82	879.21	26.38	351.68
S.B. RT.	392+99.94 (AH)		401+86.00	886.06	9.00	886.06	221.51	6.65	88.61
S.B. RT.	402+54.00		415+00.00	1246.00	9.00	1246.00	311.50	9.35	124.60
S.B. MEDIAN	206+50.00		211+74.00	524.00	4.00	232.89	58.22	1.75	23.29
S.B. MEDIAN	217+00.00		221+87.00	487.00	4.00	216.44	54.11	1.62	21.64
S.B. MEDIAN	221+87.00		226+60.00	473.00	4.00	210.22	52.56	1.58	21.02
S.B. MEDIAN	227+40.00		236+08.00	868.00	3.00	289.33	72.33	2.17	28.93
S.B. MEDIAN	236+08.00		241+70.00	562.00	4.00	249.78	62.44	1.87	24.98
S.B. MEDIAN	242+20.00		250+52.00	832.00	3.00	277.33	69.33	2.08	27.73
S.B. MEDIAN	250+52.00		255+30.00	478.00	4.00	212.44	53.11	1.59	21.24
S.B. MEDIAN	256+30.00		257+42.49 (BK)	112.49	3.00	37.50	9.37	0.28	3.75
S.B. MEDIAN	257+42.06 (AH)		272+43.00	1500.94	3.00	500.31	125.08	3.75	50.03
S.B. MEDIAN	272+43.00		277+14.00	471.00	4.00	209.33	52.33	1.57	20.93
S.B. MEDIAN	277+94.00		289+56.00	1162.00	3.00	387.33	96.83	2.91	38.73
S.B. MEDIAN	289+56.00		295+28.00	572.00	4.00	254.22	63.56	1.91	25.42
S.B. MEDIAN	296+00.00		297+00.00	100.00	3.00	33.33	8.33	0.25	3.33
S.B. MEDIAN	297+00.00		317+22.00	2022.00	3.00	674.00	168.50	5.06	67.40
S.B. MEDIAN	317+22.00		321+90.00	468.00	4.00	208.00	52.00	1.56	20.80
S.B. MEDIAN	322+74.00		343+07.00	2033.00	3.00	677.67	169.42	5.08	67.77
S.B. MEDIAN	343+07.00		348+64.00	557.00	4.00	247.56	61.89	1.86	24.76
S.B. MEDIAN	349+16.00		353+87.00	471.00	3.00	157.00	39.25	1.18	15.70
S.B. MEDIAN	353+87.00		357+83.75 (BK)	396.75	4.00	176.33	44.08	1.32	17.63
S.B. MEDIAN	357+83.17 (AH)		358+56.00	72.83	4.00	32.37	8.09	0.24	3.24
S.B. MEDIAN	359+38.00		386+92.00	2754.00	3.00	918.00	229.50	6.89	91.80
S.B. MEDIAN	386+92.00		391+60.00	468.00	4.00	208.00	52.00	1.56	20.80
S.B. MEDIAN	392+40.00		392+99.99 (BK)	59.99	3.00	20.00	5.00	0.15	2.00
S.B. MEDIAN	392+99.94 (AH)		396+92.00	392.06	3.00	130.69	32.67	0.98	13.07
S.B. MEDIAN	396+92.00		401+64.00	472.00	4.00	209.78	52.44	1.57	20.98
S.B. MEDIAN	402+60.00		408+00.00	540.00	3.00	180.00	45.00	1.35	18.00

FILE NAME =	USER NAME = bucklesjj	DESIGNED - GAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\bucklesjj\d0218355\0570708-sht-schedule.dgn	DRAWN - BBP	REVISIED -	804			(23,24,25)RS-5	CHAMPAIGN	61	18	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISIED -	CONTRACT NO. 70708							
PLOT DATE = 12/16/2010	DATE - 12/09/10	REVISIED -	SCALE: NONE			SHEET NO. 4 OF 14 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		