

VERMILION COUNTY STRUCTURES

ACTUAL MEASUREMENTS

VERMILION COUNTY STRUCTURES SCHEDULE OF QUANTITIES																							
ACTUAL MEASUREMENTS																							
SN	ROUTE CARRIED	FEATURE CROSSED	SIMS INFORMATION		DECK			APPROACH SLABS					PARAPETS (HUB, FACE & TOP)				TYPE B CURB (FACE & TOP)			GRAND TOTAL (SQ YD)	RURAL	URBAN	
					LENGTH (E-E)	WIDTH (F-F)	TOTAL AREA (SY)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (O-O)	TOTAL AREA (SY)	HEIGHT	LENGTH		TOTAL AREA (SY)	HEIGHT	LENGTH				TOTAL AREA (SY)
			LENGTH	WIDTH										3.6 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)		9 INCH TYPICAL	ALONG APPR. PVT.				
092-0003	I-74 (EB)	MIDDLEFORK VERM RIV	364.5	36.7	362.2	33.5	1348.1	30.0	12	33.5	18.0	33.5	223.3	3.60	362.2	12.0	308.9	0.75	18.0	6.0	1887.0	X	
092-0004	I-74 (WB)	MIDDLEFORK VERM RIV	364.5	36.7	362.2	33.5	1348.1	30.0	12	33.5	18.0	33.5	223.3	3.60	362.2	12.0	308.9	0.75	18.0	6.0	1887.0	X	
092-0006	I-74 (EB)	SALT FORK VERM RIVER	750.2	36.0	750.2	32.8	2734.1	0.0	0	32.8	0.0	36.0	0.0	3.60	750.2	12.0	619.4	0.00	0.0	0.0	3354.0		X
092-0007	I-74 (WB)	SALT FORK VERM RIVER	750.2	36.0	750.2	32.8	2734.1	0.0	0	32.8	0.0	36.0	0.0	3.60	750.2	12.0	619.4	0.00	0.0	0.0	3354.0		X
092-0008	I-74 (EB)	N&S & FAU 7026(L ST)	277.4	43.2	275.1	40.0	1222.5	20.0	12	40.0	8.0	40.0	177.8	3.60	275.1	12.0	239.3	0.75	8.0	2.7	1643.0		X
092-0009	I-74 (WB)	N&S & FAU 7026(L ST)	317.5	51.2	315.2	48.0	1680.9	20.0	12	55.0	8.0	55.0	244.4	3.60	315.2	12.0	271.3	0.75	8.0	2.7	2200.0		X
092-0010	I-74 (EB)	"G" ST(FAU 7026)	117.6	44.0	115.3	40.8	522.6	30.0	12	40.8	18.0	40.8	272.0	3.60	115.3	12.0	111.4	0.75	18.0	6.0	912.0		X
092-0011	I-74 (WB)	"G" ST(FAU 7026)	117.6	44.0	115.3	40.8	522.6	30.0	12	40.8	18.0	40.8	272.0	3.60	115.3	12.0	111.4	0.75	18.0	6.0	912.0		X
092-0012	I-74 (WB)	CNRL & FR1563 & 1611	237.8	44.7	235.5	41.5	1085.8	22.2	12	41.5	10.2	41.5	204.7	3.60	235.5	12.0	207.6	0.00	10.2	0.0	1499.0		X
092-0013	I-74 (EB)	CNRL & FR1563 & 1611	237.8	55.0	235.5	53.5	1399.7	24.4	12	53.5	12.4	53.5	290.1	3.60	235.5	12.0	207.6	0.00	12.4	0.0	1898.0		X
092-0014	I-74 (WB)	VERMILION RIVER	583.8	43.2	581.5	40.0	2584.3	56.5	12	40.0	44.5	40.0	502.2	3.60	581.5	12.0	484.4	0.00	44.5	0.0	3571.0		X
092-0015	I-74 (EB)	VERMILION RIVER	583.8	43.2	581.5	44.1	2849.2	57.7	12	44.1	45.7	44.1	565.5	3.60	581.5	12.0	484.4	0.00	45.7	0.0	3900.0		X
092-0018	I-74 (EB)	STONY CREEK	257.0	42.2	254.7	39.0	1103.6	50.0	15	39.0	35.0	40.0	441.1	3.60	254.7	15.0	227.7	0.00	35.0	0.0	1773.0		X
092-0019	I-74 (WB)	STONY CREEK	257.0	42.2	254.7	39.0	1103.6	50.0	15	39.0	35.0	40.0	441.1	3.60	254.7	15.0	227.7	0.00	35.0	0.0	1773.0		X
092-0023	I-74(WB)&RAMP	CSX RR & MS 9010	271.0	63.8	268.7	60.6	1809.0	50.0	15	60.6	35.0	60.6	673.3	3.60	268.7	15.0	238.9	0.75	35.0	11.7	2733.0		X
092-0024	I-74(EB)	CSX RR & MS 9010	271.0	43.2	268.7	40.0	1194.1	50.0	15	40.0	35.0	40.0	444.4	3.60	268.7	15.0	238.9	0.75	35.0	11.7	1890.0		X
092-0025	I-74 (WB)	RAMP 22.31	157.6	43.7	155.3	40.5	698.7	50.0	15	40.5	35.0	40.5	450.0	3.60	155.3	15.0	148.2	0.75	35.0	11.7	1309.0		X
092-0026	I-74 & RAMP	RAMPS 21.94/22.31	157.6	51.8	155.3	48.6	838.5	50.0	15	48.6	35.0	48.6	540.0	3.60	155.3	15.0	148.2	0.75	35.0	11.7	1539.0		X
GRAND TOTALS (SQ YD):																				38,034	3,774	34,260	

FILE NAME =	USER NAME = ceerlockjd	DESIGNED - TJB	REVISED -
ct:\pw\work\p\dot\ceerlockjd\0185207\0920026\70861-sht-schedule.dgn		DRAWN - BBP	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/15/2010	DATE - 09/20/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**VERMILION COUNTY STRUCTURES
ACTUAL MEASUREMENTS**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

*FY2011 BRIDGE DECK SEALING	
**CHAMPAIGN, MCLEAN & VERMILION	
SECTION	COUNTY
74	**
TOTAL SHEETS	SHEET NO.
19	18
CONTRACT NO. 70861	
ILLINOIS FED. AID PROJECT	