

## GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.09A

ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

G.N.-703A

SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-703-SPL

PAINT WILL NOT BE ALLOWED TO BE USED FOR SHORT TERM PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKINGS. PAVEMENT MARKING TAPE SHALL BE USED AT ALL LOCATIONS WHERE WORK ZONE PAVEMENT MARKINGS ARE CALLED OUT IN THE PLANS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-781-SPL

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE). THE RAISED REFLECTIVE PAVEMENT MARKERS ON I-74 SHALL BE PLACED ONE (EACH) AT EVEN SPACING IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPS.

NO COMMITMENTS

\*\* DEWITT & PIATT  
\*\*\* F.A.I. 74 & F.A.P. 721

FILE NAME =	USER NAME = berganAJ	DESIGNED -	AJB 11/24/2010	REVISED -	-----	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cs:\pwork\pwidot\berganaj\d0243642\0570890-sht-gennote.CEL		DRAWN -	----	REVISED -	-----			***	(74-2) & (113) I	**	15	4	
		CHECKED -	----	REVISED -	-----			CONTRACT NO. 70890					
		PLOT DATE = 12/13/2010	DATE -	-----	REVISED -			-----	ILLINOIS FED. AID PROJECT				
						SCALE: -----	SHEET NO. 1 OF 1 SHEETS	STA. -----		TO STA. -----			