

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005	50%-50% STATE-CITY 0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38	38	
20200100	EARTH EXCAVATION	CU YD	29	29	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5.6	5.6	
20400800	FURNISHED EXCAVATION	CU YD	319	319	
21400100	GRADING AND SHAPING DITCHES	FOOT	80	80	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10	
28100105	STONE RIPRAP, CLASS A3	SQ YD	18	18	
28100107	STONE RIPRAP, CLASS A4	SQ YD	235	235	
28200200	FILTER FABRIC	SQ YD	252	252	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	56	56	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	574	574	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12724	12381	343
40600300	AGGREGATE (PRIME COAT)	TON	255	248	7
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5353	5209	144
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	236	236	
40600990	TEMPORARY RAMP	SQ YD	270	270	
40603085	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N70	TON	209	209	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	10405	10117	288
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	294	263	31
44000100	PAVEMENT REMOVAL	SQ YD	65	65	

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005	50%-50% STATE-CITY 0005
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	28980	25555	3425
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SO YD	3637	3637	
44000300	CURB REMOVAL	FOOT	35	35	
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	308	308	
44200929	CLASS B PATCHES, TYPE I, 8 INCH	SO YD	21	21	
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SO YD	232	232	
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SO YD	380	380	
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	8	8	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	643	643	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	132	132	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	120	120	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4104	4104	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	182	182	
50800105	REINFORCEMENT BARS	POUND	60	60	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1	
54002050	EXPANSION BOLTS 3/4 INCH X 9 INCH	EACH	7	7	
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	11.8	11.8	
54248510	CONCRETE COLLAR	CU YD	0.8	0.8	
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.5	212.5	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
*63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	37.5	37.5	

\*SPECIALTY ITEM

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\pwidot\swartzw\d0177935\d77	448-shr-sq.dgn	DRAWN -	REVISED -		328	104 RS-4	WAYNE	77	4				
PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -	REVISED -		SCALE: NA			SHEET NO. 1 OF 2 SHEETS		STA.	TO STA.	CONTRACT NO. 74448	
PLOT DATE = 12/27/2010	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT								