


SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE 0014		
20200500 35400300	EARTH EXCAVATION (WIDENING) PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	CU YD SQ YD	91 408	91 408		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11	11		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	12	12		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	106	106		
44004250	PAVED SHOULDER REMOVAL	SQ YD	272	272		
50102400	CONCRETE REMOVAL	CU YD	27.3	27.3		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27.3	27.3		
50300260	BRIDGE DECK GROOVING	SQ YD	2744	2744		
50300300	PROTECTIVE COAT	SQ YD	3055	3055		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2260	2260		
50800515	BAR SPLICERS	EACH	22	22		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	44	44		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	120	120		
70106700	TEMPORARY RUMBLE STRIPS	EACH	3	3		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	40	40		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	900	900		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2682	2682		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	613	613		
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	3,029	3,029		
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	3029	3029		
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	3,029	3,029		
Z0015802	PLUG EXISTING DECK DRAINS	EACH	212	212		
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	2	2		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	142	142		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	84	84		
Z0018000	DRAINAGE SCUPPERS (SPECIAL)	EACH	20	20		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	44	44		

*SPECIALTY ITEM
 REVISED 3-1-11

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			774	(102BR)BR-2	Shelby	19	3	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			SCALE:		SHEET NO. OF SHEETS STA.		TO STA.	
	PLOT DATE = #DATE#	DATE -	REVISED -			CONTRACT NO. 74483 ILLINOIS FED. AID PROJECT					