

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. 20% ST. 0005
CODE NO	ITEM	UNIT		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15891	15891
40600300	AGGREGATE (PRIME COAT)	TON	318	318
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	53	53
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	15573	15573
44000155	HOT-MIX ASPHALT SURFACE REMOVAL. 1 1/2"	SQ YD	158906	158906
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	4208	4208
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	2666	2666
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	3890	3890
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	17877	17877
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	135537	135537
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1986	1986
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	135632	135632
X0556100	PARTIAL DEPTH PATCHING (SPECIAL)	SQ YD	11352	11352
● Z0076600	TRAINEES	HOUR	500	500
Z0004810	HOT-MIX ASPHALT FOR PATCHING	TON	3814	3814

*SPECIALTY ITEM
● 8842

FILE NAME *	USER NAME = #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL*		DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	95	(5,6)RS-2A	JASPER	19	3
		CHECKED -	REVISED -					CONTRACT NO. 74506					
		DATE -	REVISED -					ILLINOIS FED. AID PROJECT					