

EARTHWORK SCHEDULE

LOCATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT	EARTH EXCAVATION	EARTH EXCAVATION TO BE USED AS EMBANKMENT ADJUSTED FOR SHRINKAGE *	EMBANKMENT *	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
IL 13/15			1,511	1,284	238	1,047
CITY STREET	183	121	450	383	865	-483
ACCESS ROAD R1			1,350	1,148	122	1,027
SCHEDULE TOTAL	183	121	3,311	2,815	1,225	1,591

NOTES:

- SHRINKAGE FACTOR USED = 15%
- (*) PROVIDED FOR INFORMATION ONLY.
- IF QUANTITY FOR EARTHWORK BALANCE IS NEGATIVE (-), THEN THIS QUANTITY IS TO BE PAID FOR AS FURNISHED EXCAVATION.
- EMBANKMENT FOR ACCESS ROAD R1 INCLUDES CA-6 BACKFILL OF CURB AND GUTTER PER PLANS.

DRAINAGE STRUCTURE SCHEDULE

STR. NO	STA	OFFSET	RIM ELEV.	INVERT ELEVATION				CB TC MED INL 604101 (EACH)	CB TA 4 DIA T15F&L (EACH)	MAN TA 4 DIA T1F CL (EACH)	INLETS TA T15F&L (EACH)	INLETS TA SPL T3F&G (EACH)
				N	S	E	W					
1	134+50.00	24.30 RT	496.75			494.00		1				
2	135+03.90	28.10 RT	497.48		493.62		493.72		1			
3	136+92.70	22.80 RT	497.69			490.83	492.83		1			
4	136+50.00	22.7 RT	497.77			493.26				1		
5	10+52.00	21.95 RT	496.90								1	
6	10+52.00	37.37 LT	496.66								1	
								1	1	1	1	2

STORM SEWER SCHEDULE

PIPE RUN	SIZE (INCHES)	FROM STR.	TO STR.	SLOPE (%)	SS CL A T1 15 (FOOT)	SS CL A T1 24 (FOOT)	SS CL A T2 15 (FOOT)
1	24	1	2	0.55		51.0	
2	15	3	EX. CULV	1.67			3.0
3	15	4	3	1.00	40.0		
			TOTAL		40.0	51.0	3.0

PRECAST CONCRETE BOX CULVERT 5'X3'

FROM STA.	OFFSET	TO STA.	OFFSET	LENGT H	BOX CULVERT END SECTION, CULVERT NO. 1 (EACH)
10+52.00	38.3 RT	10+52.00	54.10 LT	92.4	2
			ROUNDED TOTAL	93.0	2

PIPE CULVERT REMOVAL

FROM STA.	OFFSET	TO STA.	OFFSET	LENGTH (FOOT)
139+64.06	244.04 LT	140+14.30	201.75 LT	65.7
			TOTAL	65.7
			ROUNDED	66.0

REMOVING CATCH BASINS

STA.	OFFSET	QTY (EA)
135+03.92	28.1 RT	1

PIPE UNDERDRAINS 4"

FROM STA.	OFFSET	TO STA.	OFFSET	LENGTH (FOOT)	REMARKS
133+85.30	44.5 RT	135+32.30	27.9 RT	147.9	CONNECT TO EX UNDERDRAIN
135+32.30	27.9 RT	136+92.70	24.0 RT	160.4	CONNECT TO STRUCTURE
136+92.70	24.0 RT	139+22.70	23.0 RT	230.0	CONNECT TO STRUCTURE
			TOTAL	538.4	
			ROUNDED	539.0	

MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID

STATION	OFFSET	QTY (EACH)
139+92.58	88.63 RT	1
	TOTAL	1

INLETS TO BE ADJUSTED

STA	OFFSET	QTY (EACH)
141+68.68	27.92 LT	1
141+77.00	21.46 LT	1
142+59.69	21.46 LT	1
143+95.07	21.46 LT	1
145+26.65	21.46 LT	1
	TOTAL	5

UNDERDRAIN REPAIR

DESCRIPTION	FROM STA.	OFFSET	TO STA.	OFFSET	LENGTH (FOOT)	ROUNDED LENGTH (FOOT)	QUANTITY (EACH)
PIPE UNDERDRAIN REMOVAL	138+89.24	69.55 RT	138+89.19	81.42 RT	11.9	12.0	-
PIPE UNDERDRAINS 4" (SPECIAL)	138+89.24	69.55 RT	138+89.19	84.54 RT	15.0	15.0	-
REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	138+89.19	81.42 LT	138+89.00	84.5 RT	-	-	1

TRENCH BACKFILL

LOCATION	QTY (CU YD)
PIPE 1	0.3
PIPE 2	1.2
PIPE 3	9.1
CULVERT NO. 1	141.0
TOTAL	151.6
ROUNDED	152.0

REMOVALS SCHEDULE

STATION	OFFSET	STATION	OFFSET	PAVEMENT REMOVAL (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	GUTTER REMOVAL (FOOT)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	MEDIAN REMOVAL (SQ FT)	FENCE REMOVAL (FOOT)
135+00.0		138+00.0		385.6					
138+00.0		143+00.0		765.9					
143+00.0		145+30.0		51.7					
136+94.4	60.5 RT	137+90.2	59.5 RT		106.4				
139+02.1	59.5 RT	140+86.6	59.5 RT		205.0				
138+91.2	11.1 LT	140+86.6	11.2 LT		217.1				
133+85.3	44.5 RT	137+06.4	29.1 RT		214.1				
133+85.3	11.9 RT	137+07.4	29.1 RT		214.7				
141+76.7		145+30.0				353.3			
137+69.4	RT						229.3		
140+16.1	RT						161.6		
142+26.6	LT						64.3		
143+64.5	LT						28.0		
144+92.1	LT						32.4		
137+76.9		142+04.2						4,232.9	
142+38.5		145+30.0						4,622.5	
139+47.3	103.61 RT	139+96.3	103.91 RT						49.0
139+96.3	103.92 RT	140+31.3	109.06 RT						35.4
140+31.3	109.06 RT	142+06.2	146.66 RT						178.9
142+06.2	146.66 RT	142+60.6	148 RT						54.5
142+60.6	148.05 RT	142+59.9	251.3 RT						103.3
		TOTAL		1,203.2	957.4	353.3	515.7	8,855.4	421.0
		ROUNDED		1,204.0	958.0	354.0	516.0	8,856.0	421.0