SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005	50% STATE 50% CITY 0005	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	18		18	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.8	3	0.8	
40600300	AGGREGATE (PRIME COAT)	TON	17	13.6	3.4	
40600990	TEMPORARY RAMP	SQYD	73	40	33	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	946	757.4	188.6	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2243		2243	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9,015	9,015		
44000300	CURB REMOVAL	FOOT	160		160	
44000400	GUTTER REMOVAL	FOOT	110	110		
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	72	72		
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	48	48		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6200	6200		
60602800	CONCRETE GUTTER, TYPE B	FOOT	110	110		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	160		160	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
~~70100460~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701306~~	~~L SUM~~	~~1~~	~~1~~		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	554	554		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,237	10,237		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3597.1	3597.1		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31.2	31.2		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10237	10237		
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	790	790		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	84	84		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	118	118		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	383.6	383.6		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	118	118		
80300100	LOCATING UNDERGROUND CABLE	FOOT	12	12		
88600600	DETECTOR LOOP REPLACEMENT	FOOT	272	272		
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	379	379		
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	790	790		
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	84	84		

*SPECIALTY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT				

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN -	REVISED -	
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -	
	PLOT DATE = $DATE$	DATE -	REVISED -	

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
829	103RS	MONROE	16	3
		CONTRACT NO. 76098		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT