

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE			CODE NO	ITEM	UNIT		0005 80% FED 20% STATE		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1.8	1.8			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.2	13.2			70300100	SHORT TERM PAVEMENT MARKING	FOOT	27684	27684		
40600300	AGGREGATE (PRIME COAT)	TON	64	64			70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	36021	36021		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3000	3000			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	351	351		
40600990	TEMPORARY RAMP	SQ YD	150	150			70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	46	46		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	5329	5329			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3076	3076		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3553	3553			*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36021	36021		
40800030	AGGREGATE (PRIME COAT)	TON	3	3			*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	351	351		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	67	67			*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	46	46		
44004250	PAVED SHOULDER REMOVAL	SQ YD	5.3	5.3			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	240	240		
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	286	286			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16		
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	40	40			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	36	36			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	240	240		
44201297	DOWEL BARS 1"	EACH	11	11			200076600	TRAINEES	HOUR	500	500		
44213200	SAW CUTS	FOOT	849	849			63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
44213202	TIE BARS 1"	EACH	14	14									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2100	2100									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	353	353									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4708	4708									
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	5.3	5.3									
50300225	CONCRETE STRUCTURES	CU YD	1.4	1.4									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	291	291									
60100080	FRENCH DRAINS	CU YD	1.8	1.8									
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	5.3	5.3									
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1104	1104									
*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4									
63200310	GUARDRAIL REMOVAL	FOOT	1100	1100									
64200105	SHOULDER RUMBLE STRIPS	FOOT	25216	25216									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

▲ REVISÉD 2/28/11  
 ● 00042  
 \* SPECIALTY ITEM

FILE NAME :	USER NAME : *USER*	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 322	SECTION 14.1585-1	COUNTY CLINTON	TOTAL SHEETS 20	SHEET NO. 3
*FILE#	PLOT SCALE : *SCALE*	DRAWN - ---	REVISED - ---							
	PLOT DATE : *DATE*	CHECKED - ---	REVISED - ---							
		DATE - ---	REVISED - ---							

