

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% STATE URBAN		CODE NO	ITEM	UNIT	TOTAL QUANTITIES		
44000400	GUTTER REMOVAL	FOOT	1958	1958							
44004250	PAVED SHOULDER REMOVAL	SO YD	3471	3471							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	213	213							
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	3471	3471	⚠						
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	10	10							
60602500	CONCRETE GUTTER, TYPE A	FOOT	1511	1511							
64200105	SHOULDER RUMBLE STRIPS	FOOT	7521	7521							
67100100	MOBILIZATION	L SUM	1	1							
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1							
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1							
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1171	1171							
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	12884	12884							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	390	390							
78300100	PAVEMENT MARKING REMOVAL	SO FT	4295	4295							
X0325866	CENTER LINE - RUMBLE STRIP	FOOT	6442	6442							
*X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19884	19884							

*SPECIALTY ITEM

⚠ REVISED 2-23-11

FILE NAME =	USER NAME = burnsideem	DESIGNED - ---	REVISED - ---
es:\pwork\pwork\burnsideem\d0207461\d076e35-shr-plan.dgn		DRAWN - ---	REVISED - ---
	PLOT SCALE = 41.2487' / 1" IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = 12/14/2010	DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9122	302-1-3	MADISON	10	3
FED. ROAD DIST. NO. _____ ILLINOIS			CONTRACT NO. 76E35	
FED. AID PROJECT				