

SUMMARY OF QUANTITIES (CONTINUED)

CODE NO.	ITEM	CONST. TYPE CODE 0021	
		UNIT	TOTAL QUANTITIES 90% FED 10% STATE
50105220	PIPE CULVERT REMOVAL	FOOT	150
50200100	STRUCTURE EXCAVATION	CU YD	1368
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20705
54003000	CONCRETE BOX CULVERTS	CU YD	93
54010808	PRECAST CONCRETE BOX CULVERTS 8' X 8'	FOOT	180
542A0217	PIPE CULVERT, CLASS A, TYPE 1 12"	FOOT	33
542A0223	PIPE CULVERT, CLASS A, TYPE 1 18"	FOOT	11
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
54248510	CONCRETE COLLAR	CU YD	0.64
550A0050	STORM SEWER CLASS A, TYPE 1 12"	FOOT	67
550A0410	STORM SEWER CLASS A, TYPE 2 24"	FOOT	164
55100500	STORM SEWER REMOVAL 12"	FOOT	43
55100900	STORM SEWER REMOVAL 18"	FOOT	94
60602500	CONCRETE GUTTER, TYPE A	FOOT	990
63200310	GUARDRAIL REMOVAL	FOOT	342
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	27
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT TERM PAVEMENT MARKING	FOOT	322
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	41
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8250
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	555
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	63
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3579
* 72000100	SIGN PANEL - TYPE 1	SQ FT	98
* 72000200	SIGN PANEL - TYPE 2	SQ FT	105
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	41
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8250
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	555
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	63

* SPECIALTY ITEM

FILE NAME =	USER NAME = nnaasdp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (CONTINUED)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvc\work\pvc\dot\nnaasdp\d0125145\d978115.sht.msc.dgn	DRAWN -	REVISED -	132			102 (N,L)	MASSAC	79	5	
PLOT SCALE = 40,0000' / 1" IN.	CHECKED -	REVISED -	CONTRACT NO. 78116							
PLOT DATE = 12/20/2010	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO. OF SHEETS STA. TO STA.					