

PAVEMENT MARKING SCHEDULE
FAI 64 EASTBOUND LANES AND RAMPS

LOCATION STATION TO STATION	LENGTH (INFORMATION ONLY)	PREFORMED PLASTIC LINE 6"	PREFORMED PLASTIC LINE 4"		PREF. PLASTIC LINE 8" (ON RAMP GOSES)	SHORT-TERM PAVEMENT MARKING		TEMP PAVT MRK - LINE 6"	TEMP PAVT MRK - LINE 4"	TEMP PAVT MRK - LINE 8"	NOTES
		WHITE (SKIP-DASH)	SOLID YELLOW (LT EOP)	SOLID WHITE (RT EOP)	SOLID WHITE	MAINLINE SKIP-DASH	SHOULDER SKIP-DASH	MAINLINE SKIP-DASH	SHOULDER STRIPE	GORE STRIPE	
FAI 64 (I-64) EASTBOUND		FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	
MAINLINE											
	5800+32.00 TO 5827+88.96	2757	690			440		690			
LT	5800+32.00 TO 5827+88.96	2757	2757						2757		
RT	5800+32.00 TO 5801+20.00	88		88			4		88		RT. 10' SHLD.
RT	5804+26.39 TO 5808+05.52	379			380					380	
RT	5808+05.00 TO 5819+90.00	1185		1185			48		1185		RT. 10' SHLD.
RT	5819+90.00 TO 5821+30.00	140			140					140	
OMIT STR. NO. 097-0001											
	5830+83.04 TO 5875+27.05	4444	1110			712		1110			
LT	5830+83.04 TO 5875+27.05	4444	4444						4444		
RT	5830+83.04 TO 5875+27.05	4444		4444			180		4444		
RAMP D											
RT	401+21.10 TO 428+15.00	2694		2694			108		2694		RT. 6' SHLD.
LT	404+20.38 TO 408+00.00	380			380					380	
LT	408+00.00 TO 428+15.00	2015	2015						2015		
RAMP C											
LT	303+04.00 TO 320+00.00	1696	1696						1696		
LT	320+00.00 TO 321+35.00	135			135					135	
RT	303+04.00 TO 327+92.00	2488		2488			100		2488		RT. 6' SHLD.
LT	321+34.00 TO 325+00.00	366	100					100			
SUBTOTALS			1900	10912	10899	1035	1152	439	1900	21811	1035
EASTBOUND TOTALS			1900	21811		1035	1591		1900	21811	1035