



WELCH ROAD SUPERELEVATION RATES			
STATION	LEFT SUPER	RIGHT SUPER	REMARKS
81+40.38	-2.00%	-2.00%	NORMAL CROWN
81+68.38	0%	-2.00%	
81+96.38	2.00%	-2.00%	FULL SUPER
82+23.38	4.00%	-4.00%	MAX SUPER
82+41.29	4.00%	-4.00%	MAX SUPER
82+68.29	2.00%	-2.00%	FULL SUPER
82+96.29	0%	-2.00%	
83+24.29	-2.00%	-2.00%	NORMAL CROWN

- \* PC 82+02.63
- \* PT 82+62.04

FILE - S:\PROJECTS\116909\_JoDaviesCo-ScoutCampRoad.DESIGN\STRUCT\TYPICAL.DGN

REV.	DATE	BY	REMARKS

DRAWN	X.X.X.
CHECKED	X.X.X.
APPROVED	X.X.X.

**JO DAVIESS COUNTY  
SCOUT CAMP ROAD AND  
WELCH ROAD IMPROVEMENTS**

**WILLETT,  
HOFMANN &  
ASSOCIATES, INC.**  
CONSULTING ENGINEERS  
Land Surveying - Transportation - Structural  
Environmental - Architecture  
809 East Second Street Dixon, Illinois 61021  
Phone 815.284.3381 Fax 815.284.3385  
Design Firm #184-00018  
www.willetthofmann.com

F.A.S. 73  
FED. AID PROJECT -  
FED. ROAD DIST. NO. 7 ILLINOIS

**TYPICAL SECTIONS, GENERAL NOTES,  
AND CONTROL POINTS**

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00133-00-BR	JO DAVIESS	48	5
STA.	- STA.		
WHA PROJECT: 1169D09		DATE: XX/XX/XXXX	