

STONE DUMPED RIPRAP, CLASS A3		
STATION	SQ YD	REMARKS
SCOUT CAMP ROAD		
R 22+69 TO 22+89	15	
PROJECT TOTAL	15	

28100705

AGGREGATE BASE COURSE, TYPE B		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
PEL 22+50	37	8"
Contingency Item	30	As Directed by the Engineer
PROJECT TOTAL	67	

35101400

HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	3	1 1/2" (TAPER)
10+62.14 TO 13+18.37	54	1 1/2" (MAINLINE)
14+01.63 TO 24+08.63	212	1 1/2" (MAINLINE)
24+08.63 TO 24+50.00	8	1 1/2" TAPER
SUBTOTAL:	277	
WELCH ROAD		
80+50.00 TO 81+11.59	10	1 1/2" (TAPER)
81+11.59 TO 83+01.18	33	1 1/2" (MAINLINE)
83+01.18 TO 83+39.00	12	1 1/2" (INCLUDES RADII)
SUBTOTAL:	55	
CALCULATIONS BASED ON 115# / SY / INCH		
PROJECT TOTAL	332	

40603000

SUB-BASE GRANULAR MATERIAL, TYPE B		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	15	8" (TAPER)
10+62.14 TO 13+18.37	311	8" (MAINLINE)
14+01.63 TO 24+08.63	1,218	8" (MAINLINE)
24+08.63 TO 24+50.00	49	8" TAPER
SUBTOTAL:	1,593	
WELCH ROAD		
80+50.00 TO 81+11.59	57	8" (TAPER)
81+11.59 TO 83+01.18	192	8" (MAINLINE)
83+01.18 TO 83+39.00	67	8" (INCLUDES RADII)
SUBTOTAL:	316	
PROJECT TOTAL	1,909	

31101000*

BITUMINOUS MATERIALS (PRIME COAT)		
STATION	GALLON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	12	0.4 GAL/SQ YD ON AGG (TAPER)
10+62.14 TO 13+18.37	251	0.4 GAL/SQ YD ON AGG (MAINLINE)
14+01.63 TO 24+08.63	985	0.4 GAL/SQ YD ON AGG (MAINLINE)
24+08.63 TO 24+50.00	39	0.4 GAL/SQ YD ON AGG (TAPER)
10+50.00 TO 10+62.14	3	0.1 GAL/SQ YD ON BIT (TAPER)
10+62.14 TO 13+18.37	63	0.1 GAL/SQ YD ON BIT (MAINLINE)
14+01.63 TO 24+08.63	246	0.1 GAL/SQ YD ON BIT (MAINLINE)
24+08.63 TO 24+50.00	10	0.1 GAL/SQ YD ON BIT (TAPER)
PEL 22+50	32	0.4 GAL/SY ON AGG
SUBTOTAL:	1,641	
WELCH ROAD		
80+50.00 TO 81+11.59	45	0.4 GAL/SY ON AGG (TAPER)
81+11.59 TO 83+01.18	152	0.4 GAL/SY ON AGG (MAINLINE)
83+01.18 TO 83+39.00	54	0.4 GAL/SY ON AGG (INCLUDES RADII)
80+50.00 TO 81+11.59	11	0.1 GAL/SY ON BIT (TAPER)
81+11.59 TO 83+01.18	38	0.1 GAL/SY ON BIT (MAINLINE)
83+01.18 TO 83+39.00	13	0.1 GAL/SY ON BIT (INCLUDES RADII)
SUBTOTAL:	313	
PROJECT TOTAL	1,954	

40600100*

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	3	1 1/2" (TAPER)
10+62.14 TO 13+18.37	54	1 1/2" (MAINLINE)
14+01.63 TO 24+08.63	212	1 1/2" (MAINLINE)
24+08.63 TO 24+50.00	8	1 1/2" TAPER
SUBTOTAL:	277	
WELCH ROAD		
80+50.00 TO 81+11.59	10	1 1/2" (TAPER)
81+11.59 TO 83+01.18	33	1 1/2" (MAINLINE)
83+01.18 TO 83+39.00	12	1 1/2" (INCLUDES RADII)
SUBTOTAL:	55	
CALCULATIONS BASED ON 115# / SY / INCH		
PROJECT TOTAL	332	

40603310

AGGREGATE BASE COURSE, TYPE A		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	7	4" (TAPER)
10+62.14 TO 13+18.37	143	4" (MAINLINE)
14+01.63 TO 24+08.63	560	4" (MAINLINE)
24+08.63 TO 24+50.00	22	4" TAPER
SUBTOTAL:	732	
WELCH ROAD		
80+50.00 TO 81+11.59	25	4" (TAPER)
81+11.59 TO 83+01.18	86	4" (MAINLINE)
83+01.18 TO 83+39.00	30	4" (INCLUDES RADII)
SUBTOTAL:	141	
PROJECT TOTAL	873	

35100100*

AGGREGATE (PRIME COAT)		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
10+50.00 TO 10+62.14	0.1	3 LBS/SQ YD (TAPER)
10+62.14 TO 13+18.37	0.9	3 LBS/SQ YD (MAINLINE)
14+01.63 TO 24+08.63	3.7	3 LBS/SQ YD (MAINLINE)
24+08.63 TO 24+50.00	0.1	3 LBS/SQ YD (TAPER)
SUBTOTAL:	4.8	
WELCH ROAD		
80+50.00 TO 81+11.59	0.2	3 LBS/SQ YD (TAPER)
81+11.59 TO 83+01.18	0.6	3 LBS/SQ YD (MAINLINE)
83+01.18 TO 83+39.00	0.2	3 LBS/SQ YD (INCLUDES RADII)
SUBTOTAL:	1.0	
PROJECT TOTAL	5.8	

40600300*

INCIDENTAL HOT-MIX ASPHALT SURFACING		
STATION	TON	REMARKS
SCOUT CAMP ROAD		
PEL 22+50	9	2"
CALCULATIONS BASED ON 115# / SY / INCH		
PROJECT TOTAL	9	

40800050*

FILE = S:\PROJECTS\1169009\JoDaviesCo_ScoutCampRoad\DESIGN\STRUCT.CONCRETE.dgn

REV.	DATE	BY	REMARKS	DRAWN	CHECKED	APPROVED	JO DAVIESS COUNTY SCOUT CAMP ROAD AND WELCH ROAD IMPROVEMENTS		SCHEDULES OF QUANTITIES		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
				X.X.X.	X.X.X.	X.X.X.				F.A.S. 73			09-00133-00-BR	JO DAVIESS	48	8
										FED. AID PROJECT -			STA.	- STA.		
									FED. ROAD DIST. NO. 7	ILLINOIS	WHA PROJECT: 1169009		DATE: XX/XX/XXXX			