



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2022

SUBJECT FAP Route 525 (US 20)
Project NHPP-LWCT(653)
Section 2020-112-RS
Kane County
Contract No. 62L90
Item No. 4, March 11, 2022 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents of the Special Provisions.
3. Added page 87 to the Special Provisions.
4. Revised sheets 5, 6 & 24-26 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

MOWING (SPECIAL) 54
SELECTIVE CLEARING 55
WEED CONTROL, AQUATIC..... 56
WEED CONTROL, NATIVE LANDSCAPE ENHANCEMENT 57
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 59
BLENDED FINELY DIVIDED MINERALS (BDE)..... 60
COMPENSABLE DELAY COSTS (BDE)..... 61
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 65
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 67
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)..... 76
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 77
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 78
TRAINING SPECIAL PROVISIONS (BDE) 78
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 81
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 83
WEEKLY DBE TRUCKING REPORTS (BDE)..... 84
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 84
WORKING DAYS (BDE) 86
REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE 87

Revised 2/24/2022

REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE

Effective: January 1, 2002

Revised: July 1, 2015

895.05TS

This item shall consist of partial removal of an existing concrete traffic signal handhole, reconstruction to the specifications of heavy duty handhole including new frame and cover, and bringing it to grade at location(s) shown in the plans or as directed by the Engineer. This work shall consist of removing the existing handhole frame and cover and the walls of the handhole to a depth of fifteen (15) inches below the finished grade.

Upon completion of the above work, four (4) holes, four (4) inches in depth, and one-half (1/2) inch in diameter shall be drilled into the top of the remaining concrete; one hole centered into each of the four handhole walls. Four (4) #3 steel dowels eight inches in length, shall be furnished and installed in the drilled holes with a masonry epoxy.

All concrete debris shall be disposed of outside the right-of-way.

Any pavement or asphalt surface removal required to install the new concrete shall have straight and neat edges using a method approved by the Engineer. Care shall be taken to protect the existing traffic signal cable. Any cable damage shall be reported immediately and repaired as directed by the Area Traffic Signal Engineer.

All steel hooks, handhole frame, cover, and concrete shall be provided to construct a rebuilt heavy duty handhole according to applicable portions of Section 814 of the Standard Specification and as modified in 814.01TS HANDHOLES Special Provision.

Basis of Payment.

This work shall be paid for at the contract unit price each for REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE.

Added 2/24/2022