

CONSTRUCTION CODE
90% FED 10% STATE
BRIDGE
0047
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	158	158
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1037	1037
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	347	347
70301120	TEMPORARY PAVEMENT MARKING LINE 4" EPOXY	FOOT	11,610	11,610
70300221	TEMPORARY PAVEMENT MARKING, LINE 4", PAINT	FOOT	11,610	11,610
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1100	1100
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1025	1025
70600250	IMPACT ATTENUATORS, TEMPORARY, (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
70600350	IMPACT ATTENUATORS, RELOCATE, (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	3433	3433
* 78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	3433	3433
* 78011045	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	68	68



*= SPECIALTY ITEM

MODEL: D:\m\stc\1726300881\1726300881.dwg
FILE NAME: 1726300881.dwg



USER NAME = mjverheyen	DESIGNED - CRS	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN - CRS	REVISED -
PLOT DATE = 12/10/2021	CHECKED - DB/RJT	REVISED -
	DATE - 12/10/2021	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 4 SHEETS STA. 1210+35.63 TO STA. 1222+53.23

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-5B)-1	LASALLE	41	4
			CONTRACT NO. 66L74	
ILLINOIS FED. AID PROJECT				

MODEL: D:\p\it
FILE NAME: V:\1730\active\17303088\civil\training\sh12366174-hk-S003.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				90% FED 10% STATE
				BRIDGE
				0047 RURAL
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	58	58
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	86	86
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	5049	5049
X0322215	CLEANING BRIDGE SCUPPERS AND DOWNSPOUTS	EACH	6	6
X0325748	ACRYLIC COATING	SQ YD	67	67
X0325749	FIBER WRAP	SQ FT	480	480
X0326649	LINEAR DELINEATOR PANELS, 6 INCH	EACH	4	4
X0327809	LINEAR DELINEATOR PANELS, 4 INCH	EACH	16	16
* 78004640	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 8"	FOOT	68	68
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	703	703
X5870015	BRIDGE DECK CONCRETE SEALER	SQ FT	11,536	11,536
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1
Z0012148	BRIDGE DECK SCARIFICATION 3"	SQ YD	556	556



* = SPECIALTY ITEM



USER NAME = mjverheyen	DESIGNED - CRS	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN - CRS	REVISED -
PLOT DATE = 12/10/2021	CHECKED - DB/RJT	REVISED -
	DATE - 12/10/2021	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 3 OF 4 SHEETS STA. 1210+35.63 TO STA. 1222+53.23

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-5B)-1	LASALLE	41	5
			CONTRACT NO. 66L74	
ILLINOIS FED. AID PROJECT				

PAVEMENT MARKING SCHEDULE	78008310		X2700027	78300202	70300100	70300150	78011025	78011045	78100100
	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"		PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 8", CONTRAST	PAVEMENT MARKING REMOVAL - WATER BLASTING	SHORT TERM PAVEMENT MARKING	SHORT TERM PAVEMENT MARKING REMOVAL	GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 9"	RAISED REFLECTIVE PAVEMENT MARKER
LOCATION	YELLOW LANE LINE (FOOT)	WHITE LANE LINE (FOOT)	WHITE DOTTED LINE (FOOT)	(SQ FT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)
NORTHBOUND	700.1	1016.4	34.0	589.2	518.4	173.4	1716.5	34.0	6.0
SOUTHBOUND	700.1	1016.4	34.0	589.2	518.4	173.4	1716.5	34.0	6.0
TOTAL =	3433		68	1179	1037	347	3433	68	12

MAINTENANCE OF TRAFFIC	70400100	70400200	78200011	70600250	70600350
	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL REFLECTORS, TYPE C	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
LOCATION	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)
STAGE 1					
NORTHBOUND	550.0		22	1	
SOUTHBOUND	550.0		22	1	
STAGE 2					
NORTHBOUND		512.5	21		1
SOUTHBOUND		512.5	21		1
TOTAL =	1100	1025	86	2	2

GUARDRAIL SCHEDULE	78200005	X0326649	X0327809
	GUARDRAIL REFLECTORS, TYPE A	LINEAR DELINEATOR PANELS, 6 INCH	LINEAR DELINEATOR PANELS, 4 INCH
LOCATION	(EACH)	(EACH)	(EACH)
NORTHBOUND	29.0	2.0	8.0
SOUTHBOUND	29.0	2.0	8.0
TOTAL =	58	4	16

PRE-STAGING SHOULDER	31102100	48300500	44004250	60260100
	SUBBASE GRANULAR MATERIAL, TYPE C 4"	PORTLAND CEMENT CONCRETE SHOULDERS 10"	PAVED SHOULDER REMOVAL	INLETS TO BE ADJUSTED
LOCATION	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)
NORTHBOUND	200.0	1570.5	1570.5	2.0
SOUTHBOUND	53.6	1567.7	1567.7	2.0
TOTAL =	254	3139	3139	4

MAINTENANCE OF TRAFFIC TEMPORARY PAVEMENT MARKING	70300221		X7030005
	TEMPORARY PAVEMENT MARKING - LINE 4" - EPOXY PAINT		TEMPORARY PAVEMENT MARKING REMOVAL
LOCATION	YELLOW LANE LINE (FOOT)	WHITE LANE LINE (FOOT)	(SQ FT)
STAGE 1			
NORTHBOUND	1016.6	2097.0	1037.9
SOUTHBOUND	1016.6	2097.0	1037.9
STAGE 2			
NORTHBOUND	700.4	1990.3	896.9
SOUTHBOUND	700.4	1990.3	896.9
TOTAL =	11610		3870

MODEL: D:\dgn\1726300881\1726300881.dgn
FILE NAME: 1726300881\1726300881.dgn



USER NAME = cstanuch	DESIGNED - MJV	REVISED -
PLOT SCALE = 100.0000 ' / in.	DRAWN - MJV	REVISED -
PLOT DATE = 1/21/2022	CHECKED - DB/RJT	REVISED -
	DATE - 01/21/2022	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**CONSTRUCTION STAGING
SCHEDULE OF QUANTITIES**

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. 1210+35.63 TO STA. 1222+53.23

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	50(5A & 5B)BJR,BRR	LASALLE	42	8
CONTRACT NO. 66L74				
ILLINOIS FED. AID PROJECT				