

MODEL: D:\s\it  
 FILE NAME: pvt\it\dot-pw-bentley.com\PI\DOT\Documents\I\DOT-Offices\District 4\Projects\04-68F71C\DDA\al\CAD\Drawings\1D4xxxxx\CADD.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE	
				PUTNAM	COUNTY
				20% STATE	80% FEDERAL
				0005	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CA MO	1	1	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION STANDARD 701421	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION. STANDARD 701306	L SUM	1	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	10	10	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	32	32	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	109612	109612	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	232752	232752	
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	120	120	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	EACH	30	30	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	453	453	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	453	453	
X0300010	BITUMINOUS MATERIALS (FOG SEAL)	POUND	67959	67959	
X1500005	BITUMINOUS SURFACE TREATMENT. A2	SQ YD	138700	138700	
X7810400	TEMPORARY RAISED PAVEMENT MARKER	EACH	2898	2898	

2

\*= SPECIALTY ITEM

USER NAME	DESIGNED	REVISED
PLOT SCALE	DRAWN	REVISED
PLOT DATE	CHECKED	REVISED
	DATE	REVISED

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2370	178-1RS-2(1,2)RS-3	PUTNAM	10	3
CONTRACT NO. 6BF77				