

LENGTH WIDTH

BRICK PAV'T REM AND REPL	CLASS C PATCH 7" (SPECIAL)			
	TYPE 1	TYPE 2	TYPE 3	TYPE 4
SQ FT	SQ YD	SQ YD	SQ YD	SQ YD

STA. 747+25 to STA. 755+54

40	6	CL	336.0			26.7
18	6	FULL WIDTH	160.0		12.0	
8	3	LT	50.0	2.7		

STA. 755+54 to STA. 771+72

12	3	RT	70.0	4.0		
27	3	CL	145.0		9.0	
6	4	LT	48.0	2.7		
8	7	CL	90.0		6.2	

STA. 771+72 to STA. 777+00

12	4	CL	84.0		5.3	
16	6	CL	144.0		10.7	
18	11	CL	260.0			22.0
90	3	RT	460.0			30.0
19	7	LT	189.0		14.8	
7	4		54.0	3.1		
8	4		60.0	3.6		

STA. 777+00 to STA. 780+55

18	4	FULL WIDTH	120.0		8.0	
35	18	FULL WIDTH	740.0			70.0
8	6	LT	80.0		5.3	
25	4	CL	162.0		11.1	

STA. 780+55 to STA. 785+12

75	3	LT	385.0			25.0
60	12	LT	868.0			80.0
80	3	LT	410.0			26.7
80	4	LT	492.0			35.6
10	6	LT	96.0		6.7	

STA. 785+12 to STA. 788+37

120	6	RT	976.0			80.0
50	18		1040.0			100.0

STA. 788+37 to STA. 792+69

40	3	RT	210.0		13.3	
60	6	RT	496.0			40.0

LENGTH WIDTH

BRICK PAV'T REM AND REPL	CLASS C PATCH 7" (SPECIAL)			
	TYPE 1	TYPE 2	TYPE 3	TYPE 4
SQ FT	SQ YD	SQ YD	SQ YD	SQ YD

STA. 792+69 to STA. 805+50

40	3	RT	210.0		13.3	
110	4	RT	672.0			48.9
42	3	RT	220.0		14.0	
10	3	LT	60.0	3.3		
9	4	RT	66.0	4.0		
23	4	CL	150.0		10.2	
14	4	RT	96.0		6.2	
9	4	LT	66.0	4.0		
8	4	LT	60.0	3.6		
6	4	LT	48.0	2.7		
9	4	RT	66.0	4.0		
6	4	RT	48.0	2.7		
23	3	LT	125.0		7.7	
23	3	RT	125.0		7.7	
8	3	RT	50.0	2.7		
3	3	RT	25.0	1.0		
14	5	RT	112.0		7.8	
10	5	RT	84.0		5.6	
4	3	RT	30.0	1.3		
6	6	LT	64.0	4.0		

3500	3	CURB REPAIR	17510.0			
------	---	-------------	---------	--	--	--

TOTALS

28160.0	52.1	174.9	22.0	562.9
SQ FT	SQ YD	SQ YD	SQ YD	SQ YD
BRICK PAV'T REM AND REPL	TYPE 1	TYPE 2	TYPE 3	TYPE 4
	CLASS C PATCH 7" (SPECIAL)			

USE

28160.0	53.0	175.0	22.0	563.0
---------	------	-------	------	-------

FILE NAME :	USER NAME : laughlinr1	DESIGNED -	REVISED -
c:\pwork\pwidot\laughlinr1\0259086\067E30-sh1-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 "/ in.	CHECKED -	REVISED -
	PLOT DATE = Feb-18-2011 10:01:43AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1619	(C)1-1	SANGAMON	10	6
CONTRACT NO. 72E30				
[ILLINOIS] FED. AID PROJECT				