

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 57	★	COOK	75	33
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

Contract 60366
★ 2122B

SHEET NO. 5
32 SHEETS

BEAM 2

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	25.500	617.072	617.072
☉ Brg W Abut	4+64.275	25.500	617.059	617.059
A	4+74.275	25.500	617.001	617.029
B	4+84.275	25.500	616.947	616.994
C	4+94.275	25.500	616.893	616.945
D	5+04.275	25.500	616.839	616.882
E	5+14.275	25.500	616.787	616.811
☉ Pier 1	5+26.150	25.500	616.707	616.707
F	5+36.150	25.500	616.629	616.620
G	5+46.150	25.500	616.543	616.531
H	5+56.150	25.500	616.447	616.436
☉ Pier 2	5+68.650	25.500	616.315	616.315
I	5+78.650	25.500	616.199	616.219
J	5+88.650	25.500	616.074	616.114
K	5+98.650	25.500	615.940	615.992
L	6+08.650	25.500	615.798	615.847
M	6+18.650	25.500	615.645	615.677
☉ Brg E Abut	6+30.525	25.500	615.465	615.465
Bk E Abut (Exist)	6+32.942	25.500	615.431	615.431

BEAM 3

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	19.500	617.197	617.197
☉ Brg W Abut	4+64.275	19.500	617.184	617.184
A	4+74.275	19.500	617.126	617.154
B	4+84.275	19.500	617.072	617.119
C	4+94.275	19.500	617.018	617.070
D	5+04.275	19.500	616.964	617.007
E	5+14.275	19.500	616.912	616.936
☉ Pier 1	5+26.150	19.500	616.832	616.832
F	5+36.150	19.500	616.754	616.745
G	5+46.150	19.500	616.668	616.656
H	5+56.150	19.500	616.572	616.561
☉ Pier 2	5+68.650	19.500	616.440	616.440
I	5+78.650	19.500	616.324	616.344
J	5+88.650	19.500	616.199	616.239
K	5+98.650	19.500	616.065	616.117
L	6+08.650	19.500	615.923	615.972
M	6+18.650	19.500	615.770	615.802
☉ Brg E Abut	6+30.525	19.500	615.590	615.590
Bk E Abut (Exist)	6+32.942	19.500	615.556	615.556

BEAM 4

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	13.500	617.322	617.322
☉ Brg W Abut	4+64.275	13.500	617.309	617.309
A	4+74.275	13.500	617.251	617.279
B	4+84.275	13.500	617.197	617.244
C	4+94.275	13.500	617.143	617.195
D	5+04.275	13.500	617.089	617.132
E	5+14.275	13.500	617.037	617.061
☉ Pier 1	5+26.150	13.500	616.957	616.957
F	5+36.150	13.500	616.879	616.870
G	5+46.150	13.500	616.793	616.781
H	5+56.150	13.500	616.697	616.686
☉ Pier 2	5+68.650	13.500	616.565	616.565
I	5+78.650	13.500	616.449	616.469
J	5+88.650	13.500	616.324	616.364
K	5+98.650	13.500	616.190	616.242
L	6+08.650	13.500	616.048	616.097
M	6+18.650	13.500	615.895	615.927
☉ Brg E Abut	6+30.525	13.500	615.715	615.715
Bk E Abut (Exist)	6+32.942	13.500	615.681	615.681

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	7.500	617.424	617.424
☉ Brg W Abut	4+64.275	7.500	617.410	617.410
A	4+74.275	7.500	617.353	617.381
B	4+84.275	7.500	617.299	617.346
C	4+94.275	7.500	617.245	617.297
D	5+04.275	7.500	617.190	617.233
E	5+14.275	7.500	617.139	617.163
☉ Pier 1	5+26.150	7.500	617.058	617.058
F	5+36.150	7.500	616.981	616.972
G	5+46.150	7.500	616.894	616.882
H	5+56.150	7.500	616.799	616.788
☉ Pier 2	5+68.650	7.500	616.666	616.666
I	5+78.650	7.500	616.551	616.571
J	5+88.650	7.500	616.426	616.466
K	5+98.650	7.500	616.292	616.344
L	6+08.650	7.500	616.149	616.198
M	6+18.650	7.500	615.997	616.029
☉ Brg E Abut	6+30.525	7.500	615.817	615.817
Bk E Abut (Exist)	6+32.942	7.500	615.783	615.783

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	1.500	617.518	617.518
☉ Brg W Abut	4+64.275	1.500	617.504	617.504
A	4+74.275	1.500	617.446	617.474
B	4+84.275	1.500	617.392	617.439
C	4+94.275	1.500	617.338	617.390
D	5+04.275	1.500	617.284	617.327
E	5+14.275	1.500	617.233	617.257
☉ Pier 1	5+26.150	1.500	617.152	617.152
F	5+36.150	1.500	617.074	617.065
G	5+46.150	1.500	616.988	616.976
H	5+56.150	1.500	616.892	616.881
☉ Pier 2	5+68.650	1.500	616.760	616.760
I	5+78.650	1.500	616.644	616.664
J	5+88.650	1.500	616.520	616.560
K	5+98.650	1.500	616.386	616.438
L	6+08.650	1.500	616.243	616.292
M	6+18.650	1.500	616.091	616.123
☉ Brg E Abut	6+30.525	1.500	615.911	615.911
Bk E Abut (Exist)	6+32.942	1.500	615.876	615.876

☉, PGL & BONDED STAGE CONSTRUCTION JOINT

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk W Abut (Exist)	4+61.858	0.000	617.541	617.541
☉ Brg W Abut	4+64.275	0.000	617.528	617.528
A	4+74.275	0.000	617.470	617.498
B	4+84.275	0.000	617.416	617.463
C	4+94.275	0.000	617.362	617.414
D	5+04.275	0.000	617.308	617.351
E	5+14.275	0.000	617.256	617.280
☉ Pier 1	5+26.150	0.000	617.176	617.176
F	5+36.150	0.000	617.098	617.089
G	5+46.150	0.000	617.011	616.999
H	5+56.150	0.000	616.916	616.905
☉ Pier 2	5+68.650	0.000	616.784	616.784
I	5+78.650	0.000	616.668	616.688
J	5+88.650	0.000	616.543	616.583
K	5+98.650	0.000	616.409	616.461
L	6+08.650	0.000	616.266	616.315
M	6+18.650	0.000	616.114	616.146
☉ Brg E Abut	6+30.525	0.000	615.934	615.934
Bk E Abut (Exist)	6+32.942	0.000	615.900	615.900

Notes:

For Plan see Sheet 4 of 32.

DESIGNED	NDR
CHECKED	DSE
DRAWN	RTT
CHECKED	DSE
DATE	JAN 16, 2009

Illinois Firm Registration No. 184-006533



Stanley Consultants Inc.

8501 West Higgins Road, Suite T30, Chicago, Illinois 60631-2801
www.stanleygroup.com

TOP OF DECK SLAB ELEVATIONS
103RD STREET OVER
FAI 57 (DAN RYAN-WEST LEG)
FAI RTE 57 SECTION 2122B
COOK COUNTY
STA 5+47.40
STRUCTURE NO 016-2127

Q:\15960\02_103\shf\sbp\00205.dgn 15-JAN-2009