

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	9Y-RS-6	DUPAGE	41	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY				
				1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	59	59				
40600300	AGGREGATE (PRIME COAT)	TON	292	292				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	44	44				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	999	999				
40600990	TEMPORARY RAMP	SO YD	999	999				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	14285	14285				
42001300	PROTECTIVE COAT	SO YD	157	157				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	145757	145757				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	805	805				
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SO YD	92	92				
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	1150	1150				
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	575	575				
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	1150	1150				
<input type="checkbox"/> 55039700	STORM SEWERS TO BE CLEANED	FOOT	2000	2000				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	30987	30987				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2871	2871				

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY				
				1000				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	55092	55092				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4108	4108				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1458	1458				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1445	1445				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	31080	31080				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2871	2871				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55092	55092				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4108	4108				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1458	1458				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1445	1445				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2164	2164				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1840	1840				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2584	2584				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5740	5740				
XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SO FT	8200	8200				
<input type="checkbox"/> Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30				
<input checked="" type="checkbox"/> Z0076600	TRAINEES	HOUR	1500	1500				

- Y080
- * SPECIALTY ITEMS
- NON-PARTICIPATING ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 311/ US 34 (OGDEN AVE.)
 I-355 TO WARWICK AVE.

Rev.

1/9/2009 8:00am c:\paw\tdo\813\elec\08\81359.dwg