

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN 100% FED. TOTAL	EB	WB	STONY ISLAND	SFTY- 3J	BRIDGES	BRIDGES	BRIDGES	BRIDGES	BRIDGES
				ROADWAY	ROADWAY	RAMPS		SN 016-0149 SN 016-0150	SN 016-0153 SN 016-0161 SN 016-2602	SN 016-0158 SN 016-0159	SN 016-0157 SN 016-0160	SN 016-2733 SN 016-2734
					1000 - 2A			X531-2A	X231-2A	X032-2A	X131-2A	X131-2A
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	219	182							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	160,490	61,250	63,043	36,197						
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	41,033	15,374	14,133	11,526						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	9,294	3,474	3,520	2,300						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230	69	114	47						
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	2,244	804	755	685						
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	28,860	13,081	13,426	2,353						
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	2,155	801	1,354	0						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	20,593	10,267	10,326	0						
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	5,541	2,754	2,787	0						
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	5,846	2,757	3,089	0						
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	894	473	421	0						
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	59		59							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,566	1,658	1,662	246						
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	205	102	103	0						
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	508				508					
* 78200450	MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	442				442					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	1,088	544	544							
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	52				52					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	840	420	420							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,765	1,760	1,759	246						
X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SQ YD	226			226						
X0321309	CONCRETE PAD	SQ YD	78				78					
* X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1	0.5	0.5							
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	104	26	26	52						
X0322729	MATERIAL TRANSFER DEVICE	TON	41,105	16,219	17,050	7,828						
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	126						126			
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	544						126	278	140	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	39						12		27	
X0325349	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	FOOT	915				915					
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.5	0.5							
X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	1,784	283	532	969						

* SPECIALTY ITEM

FILE NAME =
DIRAC08-005-500.dgn

USER NAME = dwoznarski

DESIGNED -

REVISED -

DRAWN - DMW

REVISED -

CHECKED -

REVISED -

DATE - 2/7/2009

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BISHOP FORD EXPRESSWAY (I-94)
SUMMARY OF QUANTITIES

SCALE: N/A

SHEET NO. 3 OF 4 SHEETS

STA.

TO STA.

F.A.I.
RTE.

SECTION

COUNTY

TOTAL SHEETS

SHEET NO.

94 (0312-708W, ETC. & 1315)RS-4

COOK

167 5

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONTRACT NO. 60C08

Rev.