

**CONTRACT 60C08
GLARE SCREEN & CONCRETE REMOVAL**

WB I-94

LOCATION		CONCRETE GLARE SCREEN REMOVAL (FOOT)	CONCRETE REMOVAL (CY)
FROM STA	TO STA		
359+00	361+00	30	0.7
		30	0.7
		10	0.2
		10	0.2
I-94 EB			7.0
I-94 WB			7.0
X231 BRIDGE COLUMN			0.6
TOTAL		80	16.5

**CONTRACT 60C08
CLASS B PATCHES, 10"**

EASTBOUND RAMP

PATCH NUMBER	LOCATION	LENGTH (FT)	WIDTH (FT)	CLASS B, 10"		SAW CUTS (FT)	PAVEMENT FABRIC (SY)	DOWEL BARS (EA)	TIE BARS (EA)
				TYPE II	TYPE IV				
R1	DOLTON AVE - RAMP D	6	14	9.3		60.0		26	
R2	DOTY AVE - RAMP A	6	12	8.0		54.0		22	
R3	STONY ISLAND AVE ENTRANCE	50	17			201.0	94.4	32	98
SUBTOTAL EASTBOUND				17.3	94.5	315.0	94.4	80	98
ROUNDED SUBTOTAL EASTBOUND				18	95	315	95	80	98

WESTBOUND MAINLINE

PATCH NUMBER	STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	CLASS B, 10"		SAW CUTS (FT)	PAVEMENT FABRIC (SY)	DOWEL BARS (EA)	TIE BARS (EA)
					TYPE II	TYPE IV				
21W	163+74	OUTSIDE SHOULDER	40	15.5		68.9	166.5	68.9	29	78
ROUNDED SUBTOTAL WESTBOUND				0	69	167	69	29	78	

TOTAL		18	164	482	164	109	176
TOTAL FROM CLASS A PATCH SCHEDULE				139		44	
TOTAL ALL SCHEDULES		18	164	621	164	153	176

**CONTRACT 60C08
CLASS A PATCHES, 10"**

EASTBOUND MAINLINE

PATCH NUMBER	STATION	LANE NUMBER	LENGTH (FT)	WIDTH (FT)	CLASS A, 10"		SAW CUTS (FT)	PATCHING REINFORCEMENT (SY)	DOWEL BARS (EA)
					TYPE II	TYPE III			
11E	441+44	2	4	12	5.4		68.0	5.4	22
12E	485+88	1	5	12	6.7		71.0	6.7	22
TOTAL					12.1		139.0	12.1	44
ROUNDED TOTAL					13		139	13	44

TOTAL FROM CLASS B PATCH SCHEDULE		482		109
TOTAL ALL SCHEDULES		13	621	153

**CONTRACT 60C08
CONCRETE BARRIER WALL REMOVAL AND REPLACEMENT (FULL DEPTH REPAIR)**

EASTBOUND

LOCATION		LENGTH (FOOT)
STA	STA	
218+50	218+60	10
348+40	348+48	8
SUBTOTAL		18

WESTBOUND

LOCATION		LENGTH (FOOT)
STA	STA	
133+60	133+70	10
151+70	151+85	15
158+90	159+10	20
172+15	172+20	5
186+00	186+15	15
191+50	191+98	48
SUBTOTAL		113

TOTAL	131
--------------	------------

**CONTRACT 60C08
TEMPORARY PAVEMENT MARKING SCHEDULE**

STAGE	WET REFL. TEMP TAPE, TYPE III - LETTERS AND SYMBOLS (SQ FT)			WET REFL. TEMP TAPE, TYPE III 4" (FOOT)			WET REFL. TEMP TAPE, TYPE III 5" (FOOT)			WET REFL. TEMP TAPE, TYPE III 8" (FOOT)			WET REFL. TEMP TAPE, TYPE III 24" (FOOT)			TEMP PM LINE 6" (FOOT)			WORK ZONE PM REMOVAL (SQ FT)			PAVEMENT MARKING REMOVAL (SQ FT)		
	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY	EB	WB	STONY
STAGE 1				1,515	1,515	28,497									6,750	6,750		495	495		420	420		
STAGE 2	219	182		69,528	72,419		21,143	21,454	2,401	16,984	16,262	12,103	69	114	47									
SUBTOTAL	219	182		71,043	73,934	28,497	21,143	21,454	2,401	16,984	16,262	12,103	69	114	47	6,750	6,750		495	495		420	420	
TOTAL	401			173,474			44,998			45,349			230			13,500			990			840		