



PR PREFORMED PLASTIC PVT MKG
TYPE C, INLAID, LINE 8"
WHITE LANE LINES
3' DASH - 12' SKIP

PR PREFORMED PLASTIC PVT MKG
TYPE C, INLAID, LINE 8"
WHITE LANE LINES

NOTE:
SEE TC-12 "MULTI-LANE FREEWAY
PAVEMENT MARKING DETAILS"
FOR PLACEMENT & TYPE
OF RAISED REFLECTIVE
PAVEMENT MARKERS

- PAVEMENT MARKING LEGEND**
- A THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE EDGE LINE
 - B THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW EDGE LINE
 - C THERMOPLASTIC PAVEMENT MARKING - LINE 8" WHITE EDGE LINE
 - D THERMOPLASTIC PAVEMENT MARKING - LINE 12" PAVEMENT DIAGNOLS SPACED @ 500' CENTERS
 - E THERMOPLASTIC PAVEMENT MARKING - LINE 12" WHITE CORE DIAGNOLS SPACED @ 30' CENTERS
 - F PREFORMED PLASTIC PAVEMENT MARKING TYPE B, INLAID, LINE 4" WHITE LANE LINES - 2' DASH - 6' SKIP
 - G PREFORMED PLASTIC PAVEMENT MARKING TYPE B, INLAID, LINE 5" WHITE LANE LINES - 10' DASH - 30' SKIP
 - H POLYUREA PAVEMENT MARKING, TYPE I, LINE 4" WHITE EDGE LINE
 - I POLYUREA PAVEMENT MARKING, TYPE I, LINE 4" YELLOW EDGE LINE
 - J POLYUREA PAVEMENT MARKING, TYPE I, LINE 5" WHITE LANE LINES - 10' DASH - 30' SKIP
 - K POLYUREA PAVEMENT MARKING, TYPE I, LINE 8" WHITE EDGE LINE
 - L POLYUREA PAVEMENT MARKING, TYPE I, LINE 12" WHITE CORE DIAGNOLS SPACED @ 30' CENTERS

- GUIDE SIGN SEQUENCE NUMBERING CODE**
- DIRECTION OF TRAFFIC**
 EB - EASTBOUND I-94
 WB - WESTBOUND I-94
 SI - STONY ISLAND FEEDER RAMP
- EXAMPLE**
 EB-TR-03
- SIGN PANEL NUMBER**
- MOUNTING TYPE**
 TR - Truss
 CL - Cantilever
 BR - Bridge Mounted
 WP - Wood Post
 BS - Breakaway Steel
 LP - Light Pole
- REMOVE AND REPLACE SIGN PANEL**
- EXISTING LUMINAIRE**

FILE NAME = D168C88-874-PMK_2.dgn	USER NAME = dwoznarski	DESIGNED - DRAWN - DMW	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		BISHOP FORD EXPRESSWAY (I-94) PAVEMENT MARKING AND SIGNING PLANS		F.A.I. RTE. 94	SECTION 10312-708W, ETC. & 13151RS-4	COUNTY COOK	TOTAL SHEET SHEETS NO. 167	SHEET NO. 74
PLOT SCALE = 100.00' / IN.		CHECKED -	DATE - 2/6/2009	SCALE: 1" = 50'		SHEET NO. 2 OF 21 SHEETS		STA. 140+00 TO STA. 170+00		CONTRACT NO. 60C08		
PLOT DATE = 2/6/2009		DATE - 2/6/2009	REVISED -	FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT						