F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-94		COOK	206	103
STA.	TO STA.			

* 48(T.1,T.1A, NB-B, SB-B)R-85

TYPE "3" CABINET ON TYPE "D" FOUNDATION
6FT X 14 FT INDUCTION LOOP CENTERED ON RAMP
7FT OF 1¼IN P-DUCT

STA. 2+75

170 FT OF 2IN P-DUCT
170 FT OF 1¼ IN P-DUCT
6FT X 14FT INDUCTION LOOP CENTERED ON RAMP
39 FT OF 2IN CONDUIT PUSHED

389 FT OF 2IN P-DUCT

85 FT 2IN CONDUIT ATT. TO STR.

213 FT OF 1¼IN P-DUCT
211 FT OF 2IN P-DUCT

GB EB EXIT

GB EB EXIT

6FT X 6FT INDUCTION LOOP IN LANE 2
100 FT OF 2IN CONDUIT PUSHED

6FT X 6FT INDUCTION LOOP IN EACH LANE

CSSR, & SB R.R.

182 FT OF 1¼IN P-DUCT

IBEB EXIT

15FT OF 1¼IN P-DUCT
15 FT OF 1¼IN P-DUCT

31 FT OF 2IN CONDUIT PUSHED
31 FT OF 2IN CONDUIT PUSHED

TYPE "3" CABINET ON TYPE "D" FOUNDATION

6FT X 12 FT INDUCTION LOOP CENTERED ON RAMP
6FT X 10 FT INDUCTION LOOP CENTERED ON RAMP
73 FT OF 1¼IN P-DUCT

140FT OF 1¼IN P-DUCT
140 FT OF 1¼IN P-DUCT

TYPE "C" SERVICE INSTALLATION

130th STREET

N

LEGEND
- INDUCTION LOOP
- CABINET
- JUNCTION BOX
- PULL POINT
- SERVICE INSTALLATION
- P-DUCT
- CONDUIT
- SURVEILLANCE DUCT
- FENCE

WIRING DIAGRAM ON PAGE 1

EXISTING INSTALLATION
FOR
INFORMATION ONLY

FOR INFORMATION ONLY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TRAFFIC SYSTEMS CENTER

130th STREET INSTALLATION

PAGE 2 OF 22
SCALE 1"=30'
DATE 6-85
DRAWN BY
CHECKED BY

FILE NAME = 0160C08-148TRAFFIC SURVEILLANCE.dgn	USER NAME = dwozniarski	DESIGNED -	REVISED -
		DRAWN - DMW, GDS	REVISED -
	PLOT SCALE = N/A	CHECKED -	REVISED -
	PLOT DATE = 2/6/2009	DATE - 2/6/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BISHOP FORD EXPRESSWAY (I-94)
TRAFFIC SURVEILLANCE

SCALE: N/A | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	(0312-708W, ETC. & 1315)RS-4	COOK	167	148
		CONTRACT NO. 60C08		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		