F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1398	0405 RS-7	COOK	22	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60C57

URBAN 100% FED

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	35	35					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29	29					
40600300	AGGREGATE (PRIME COAT)	TON	145	145					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	19					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	605	605					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	45	45					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3045	3045					
42001300	PROTECTIVE COAT	SQ YD	170	170					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1060	1060					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3550	3550					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	32685	32685					
44000600	SIDEWALK REMOVAL	SQ FT	1060	1060					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	220	220					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	265	265					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	50	50					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	75	75					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	100	100					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	70	70					
△ 55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	1	1					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	45	45					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10					

△ NON-PARTICIPATING (100% STATE)

URBAN 100% FED

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5270	5270					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12390	12390					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1410	1410					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	165	165					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	830	830					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	555	555					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8755	8755					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12390	12390					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1410	1410					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	165	165					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	830	830					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	555	555					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	360	360					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	418	418					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 1/12/2009

1/12/2009
pdfpw,wsc:$PW1100$SUTHML$c0108943$0/24301-Design.dgn