

SUMMARY OF QUANTITIES			100% FED. URBAN	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	U.S. 45 BRIDGE SFTY-2A
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	44	44
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	50	50
42001300	PROTECTIVE COAT	SQ YD	449	449
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	585	585
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	449	449
50300260	BRIDGE DECK GROOVING	SQ YD	428	428
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	600	600
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	3
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1	1
78300100	PAVEMENT MARKING REMOVAL	SQ FT	40	40
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			100% FED. URBAN	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	U.S. 45 BRIDGE SFTY-2A
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,060	1,060
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6	6
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT MAST ARM	EACH	6	6
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	6	6
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	449	449
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4	4
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1,600	1,600
* X0325867	COMBINATION POLE MOUNTED ELECTRIC SERVICE BOX	EACH	1	1
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	1	1
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	449	449
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	35	35
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1

* SPECIALTY ITEM

FILE NAME = D16067-sht-500.dgn
PLOT DATE = 1/12/2009



DESIGNED -	S.J.P.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	JANUARY 12, 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
U.S. 45

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 446+29 TO STA. 461+23

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	105 B-3-I	WILL	18	3
CONTRACT NO. 60D67			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	