



GENERAL NOTES:

Plan Dimensions and Details Relative to Existing Plans are Subject to Nominal Construction Variations. The Contractor Shall Field Verify Existing Dimensions and Details Affecting new Construction and Make Necessary Approved Adjustments Prior to Construction or Ordering of Materials. Such Variations Shall not be Cause for Additional Compensation for a Change in Scope of the Work, However, the Contractor will be Paid for the Quantity Actually Furnished at the Unit Price Bid for the Work.

These Plans Have Been Prepared From Notes Received From I.D.O.T. Field Maintenance Engineers.

TOTAL BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Hot-Mix Asphalt Surface Removal (Complete)	Sq. Yd.	449
Bridge Deck Hydro-Scarification, 1/2 Inch	Sq. Yd.	449
Bridge Deck Latex Concrete Overlay, 2 1/4 Inches	Sq. Yd.	449
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	35
Bridge Deck Grooving	Sq. Yd.	428
Protective Coat	Sq. Yd.	449

CR & A
 CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS / PLANNERS / SURVEYORS
 211 W. WACKER DRIVE CHICAGO, IL 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

FILE NAME = plan.elev.sht	USER NAME = IDOT	DESIGNED - B.N.S.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN & ELEVATION U.S. 45 OVER FORKED CREEK		F.A.P. RTE. 330	SECTION 105 B-3-I	COUNTY WILL	TOTAL SHEETS 18	SHEET NO. 11
PLOT SCALE = 50.0000' / IN.	DRAWN - D.L./R.E.S./F.M.	CHECKED - B.N.S./J.C.N.	REVISED -		S.N. 099-0243		CONTRACT NO. 6067				
PLOT DATE = 1/12/2009	DATE - JANUARY 12, 2009	REVISED -			SCALE: SHEET NO. S1 OF S3 SHEETS STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
					SHEET NO. S1 OF S3 SHEETS STA. TO STA.						