

100%
FED.

CONSTRUCTION
TYPE CODE
BRIDGE
SN 016-0806

SUMMARY OF QUANTITIES

URBAN
TOTAL

SFTY-2A
QUANTITY

CODE NO.	ITEM DESCRIPTION	UNIT	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9	9
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10	10
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	108	108
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	14,500	14,500
50102400	CONCRETE REMOVAL	CU YD	717.3	717.3
50157300	PROTECTIVE SHIELD	SQ YD	2,480	2,480
50300255	CONCRETE SUPERSTRUCTURE	CU YD	763.2	763.2
50300260	BRIDGE DECK GROOVING	SQ YD	13,652	13,652
50300300	PROTECTIVE COAT	SQ YD	2,126	2,126
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	22,920	22,920
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	164	164
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	110,140	110,140
50800515	BAR SPLICERS	EACH	336	336
52000110	PREFORMED JOINT STRIP SEAL	FOOT	389	389
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	42	42
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	122	122
52100530	ANCHOR BOLTS, 1 1/4"	EACH	328	328
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CALMO	4	4
67100100	MOBILIZATION	L SUM	1	1
70101805	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,080	1,080
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,389	2,389
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	10,741	10,741
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	24	24
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	124	124
78300100	PAVEMENT MARKING REMOVAL	SQ FT	79	79
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24
X030424	SILICONE JOINT SEALER	FOOT	125	125
X0321468	PLUG EXISTING DECK DRAINS	EACH	26	26
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	14,500	14,500
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77	77
X0325115	ADJUSTING DRAINAGE SCUPPERS, TYPE B	EACH	27	27
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5" INCHES)	SQ FT	2,513	2,513
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	10,741	10,741
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	1	1
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	14,500	14,500
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	16	16
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	30	30
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	229	229
Z0070600	TRAINERS	HOUR	1500	1500
Z0034806	MODULAR EXPANSION JOINT-SWIVEL 6"	FOOT	79	79
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	22	22

* SPECIALTY ITEM

⊙ Y080

PLOT DATE = 1/14/2009
PLOT SCALE = K:\11225523\Civil\Sheets\SoD_Burnham.sht
USER NAME = JTFreedy
MODEL = Default



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE - 1-14-2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BURNHAM AVE. OVER STATE ST.
STRUCTURE NO. 016-0806

SUMMARY
OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2943	1212.8-1-1	COOK	51	3
CONTRACT NO. 60D74				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

REV.

SCALE: 1:1 SHEET NO. 3 OF 51 SHEETS STA. TO STA.