

URBAN
100% FED.

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
			LEMONT ROAD	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A
42001300	PROTECTIVE COAT	SQ YD	22,495	22,495
44213200	SAW CUTS	FOOT	247	247
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	492	492
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	412	412
44000700	APPROACH SLAB REMOVAL	SQ YD	568	568
44000100	PAVEMENT REMOVAL	SQ YD	348	348
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	516	516
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	55	55
50102400	CONCRETE REMOVAL	CU YD	190	190
50157300	PROTECTIVE SHIELD	SQ YD	1,830	1,830
50300225	CONCRETE STRUCTURES	CU YD	44.0	44.0
50200100	STRUCTURE EXCAVATION	CU YD	40	40
50300255	CONCRETE SUPERSTRUCTURE	CU YD	257.1	257.1
50300260	BRIDGE DECK GROOVING	SQ YD	20,877	20,877
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5120	5120
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	20	20
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	53,340	53,340
50800515	BAR SPLICERS	EACH	322	322
51205200	TEMPORARY SHEET PILING	SQ FT	374	374
52000110	PREFORMED JOINT STRIP SEAL	FOOT	72	72
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	2	2
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	8	8
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	10	10
52100540	ANCHOR BOLTS, 1 1/2"	EACH	40	40
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
60260100	INLETS TO BE ADJUSTED	EACH	4	4
60622000	CONCRETE MEDIAN, TYPE SM-2.12	SQ FT	3,523	3,523
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	75	75
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	106	106
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
67100100	MOBILIZATION	L SUM	1	1

20700400 POROUS GRANULAR EMBANKMENT, SPECIAL

CU YD 40 40

URBAN
100% FED.

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
			LEMONT ROAD	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,100	1,100
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	550	550
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14,580	14,580
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	17	17
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,213	1,213
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	750	750
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	245	245
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	19,330	19,330
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1,340	1,340
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	53	53
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	130	130
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	113	113
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	33	33
* 78100300	REPLACEMENT REFLECTOR	EACH	33	33
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,374	2,374
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	113	113
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	107	107
* 81700125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	17,732	17,732
* 81800410	AERIAL CABLE, 4-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4,265	4,265
* 88600100	DETECTOR LOOP, TYPE I	FOOT	605	605
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1
X0320887	POLYMER CONCRETE	CU FT	12	12
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	22,347	22,347
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	130	130
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1,172	1,172
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	19,654	19,654
X0712400	TEMPORARY PAVEMENT	SQ YD	348	348
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	1	1

*Specialty Items

FILE NAME = 60076 S00.dgn
PLOT DATE = 1/31/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - G.F.L.
DRAWN - A.C.S.
CHECKED - E.J.M.
DATE - JANUARY, 2009

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
LEMONT ROAD

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2612	3104 B-1-I-2	COOK	80	3
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	

CONTRACT NO. 60D76

Rev.