


SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000	BRIDGE X281-2A
20200100	EARTH EXCAVATION	CU YD	175	175	
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	500	500	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	45	45	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	30	30	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	230	230	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	45	45	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	730	730	
44003100	MEDIAN REMOVAL	SQ FT	2,540	2,540	
50102400	CONCRETE REMOVAL	CU YD	18.5		18.5
50157300	PROTECTIVE SHIELD	SQ YD	187		187
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20.1		20.1
50300260	BRIDGE DECK GROOVING	SQ YD	405		405
50300300	PROTECTIVE COAT	SQ YD	1,020		1,020
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,770		2,770
50800515	BAR SPLICERS	EACH	34		34
52000110	PREFORMED JOINT STRIP SEAL	FOOT	142		142
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	4,325	4,325	
67000400	ENGINEER FIELD OFFICE, TYPE A	CAL MO	4	1	3
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.2	0.8
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,800	5,800	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	725	725	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	725	725	
• 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	75	75	
• 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	17,500	17,500	
• 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	410	410	
• 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	250	250	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	30	
• 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10	
• 78100300	REPLACEMENT REFLECTOR	EACH	270	270	
• 78200530	BARRIER WALL MARKERS, TYPE C	EACH	60	60	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,400	6,400	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	30	
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	270	270	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	78	78	
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	485	485	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	17,300	17,300	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	390		390
Z0006201	BRIDGE DECK HYDRO-SCARIFICATION 1"	SQ YD	390		390
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1.1		1.1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	36.7		36.7
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

• SPECIALTY ITEM

FILE NAME = N:\PROJ\3329\3329\_28\Drawings\Proposals\3329\_28\_03\_acc.dgn

 <b>Ciorba Group, Inc.</b> CONSULTING ENGINEERS 5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656 Tel. 773.775.4009 Fax 773.775.4014	USER NAME = wjancaster	DESIGNED - JCC	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>FAP 349 / US ROUTE 30</b> <b>OVER RIVER STREET</b> <b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 349	SECTION 11 HB-I	COUNTY KENDALL	TOTAL SHEETS 26	SHEET NO. 3
	PLOT SCALE = 1/8" = 1' / IN.	CHECKED - MJL	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT	CONTRACT NO. 60D83
	PLOT DATE = 1/13/2009	DATE - 01/30/08	REVISED -							