

SUMMARY OF QUANTITIES

| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE | |
|------------|--|--------|----------------|------------------------|--|
| | | | | 100% FED | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 15.1 | 15.1 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 75.5 | 75.5 | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 3.77 | 3.77 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 110 | 110 | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 379 | 379 | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 3169.1 | 3169.1 | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 35948 | 35948 | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 100 | 100 | |
| 44002215 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4" | SQ YD | 1804 | 1804 | |
| 44201761 | CLASS D PATCHES, TYPE I, 10 INCH | SQ YD | 115 | 115 | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 1031 | 1031 | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SQ YD | 93 | 93 | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SQ YD | 329 | 329 | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 1008 | 1008 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 9125 | 9125 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 90303 | 90303 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 15050 | 15050 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 45151 | 45151 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 293 | 293 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 293 | 293 | |
| * 88600100 | DETECTOR LOOP, TYPE I | FOOT | 66 | 66 | |
| 20201006 | GRADING AND SHAPING SHOULDERS | UNIT | 253.3 | 253.3 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 52 | 52 | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 1485.60 | 1485.60 | |
| 70076600 | TRAINEES | HOUR | | | |
| 7080 | (100% FED) | | | | |

* SPECIALTY ITEM

PLT DATE : 1/12/2009
 FILE NAME : P:\2007\ME07080_Ver-Var-Phil\Cadd\06_US14\US14\Shs\03US14500.shx
 USER NAME : Millennium Engineering
 MODEL :



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.0110 voice, 630.839.2566 fax
 www.millenniaeng.com
MILLENNIA ENGINEERING

| | |
|-----------------|-----------|
| DESIGNED - TVN | REVISED - |
| DRAWN - TVN | REVISED - |
| CHECKED - RPD | REVISED - |
| DATE - 01/14/09 | REVISED - |

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 14
 BUNKER HILL RD TO PARK LANE DR**

SUMMARY OF QUANTITIES

| | | | | |
|---|---------|---------|--------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 305 | 29RS-4 | MCHENRY | 17 | 3 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 60E18 | |

SCALE: SHEET NO. OF SHEETS STA. TO STA.

P:\2007\ME07080_Ver-Var-Phil\Cadd\06_US14\US14\Shs\03US14500.shx