

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

| FILE NAME = | USER NAME = gaglianobt | DESIGNED - | REVISED - R. MIRS 09-15-97 | | | ARTERIAL ROAD | | F.A.U. | SECTION | COUNTY | TOTAL SHE | ETI |
|---------------------------|----------------------------|------------|--------------------------------|------------------------------|------------------|------------------------------|---------|--------------------------|-----------|-----------------------|-----------|-------|
| W:\distatd\22x34\tc22.dgn | | DRAWN - | REVISED - R. MIRS 12-11-97 | STATE OF ILLINOIS | | | | 2759 | 0505 RS-6 | COOK | 24 2 | 3 |
| | PLOT SCALE = 50.000 '/ IN. | CHECKED - | REVISED -T. RAMMACHER 02-02-99 | DEPARTMENT OF TRANSPORTATION | INFORMATION SIGN | | | 2100 | TC-22 | CONTRACT NO. 60E24 | | - |
| | PLOT DATE = 1/4/2008 | DATE - | REVISED - C. JUCIUS 01-31-07 | | SCALE: NONE | SHEET NO. 1 OF 1 SHEETS STA. | TO STA. | FED. ROAD DIST. NO. 1 IL | | NOIS FED. AID PROJECT | | |