F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.1B-R	COOK	101	005
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62532

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
			URBAN 100% FED X771-2A	CONSTRUCTION TYPE CODE										
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60	60										
20101000	TEMPORARY FENCE	FOOT	520	520										
20101100	TREE TRUNK PROTECTION	EACH	5	5										
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	180		180									
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	0.4	0.4										
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4										
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	37	37										
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	37	37										
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	37	37										
25100630	EROSION CONTROL BLANKET	SQ YD	2036	2036										
28000400	PERIMETER EROSION BARRIER	FOOT	537	537										
28000510	INLET FILTERS	EACH	20	20										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2										
40600300	AGGREGATE (PRIME COAT)	TON	6	6										
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.4	0.4										
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	155	155										
40600895	CONSTRUCTING TEST STRIP	EACH	2	2										
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	233	233										
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5										
42001300	PROTECTIVE COAT	SQ YD	311	311										
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	369	369										
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	140	140										
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1960	1960										
42400800	DETECTABLE WARNINGS	SQ FT	97	97										
44000100	PAVEMENT REMOVAL	SQ YD	153	153										
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2637	2637										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	423	423										
44000600	SIDEWALK REMOVAL	SQ FT	1960	1960										
44000700	APPROACH SLAB REMOVAL	SQ YD	368	368										
44200104	PAVEMENT PATCHING, TYPE I, 9 INCH	SQ YD	100	100										
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	80	80										

* DENOTES SPECIALTY ITEMS
□ NON-PARTICIPATING

BRIDGE INFORMATION

① 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TTB09MWA.DGN ..\SU0000UE.DGN ..\SU0000US.DGN
1-16-2009 10:54:23 F:\DOCUMENT\930860\CIVIL\DGN\SU0000UA.DGN
HECHTER