F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1920.1B-R	COOK	101	002
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62533

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS/ HIGHWAY STANDARDS
3 - 4	GENERAL NOTES
5 - 9	SUMMARY OF QUANTITIES
10 - 11	TYPICAL SECTIONS/ BITUMINOUS CONCRETE MIX SCHEDULE
12 - 14	SCHEDULE OF QUANTITIES
15	ALIGNMENT AND TIES
16	112TH PL EXISTING AND PROPOSED PLAN AND PROFILE
17	HAMLET AVE EXISTING AND PROPOSED ROADWAY
18	112TH PL BRIDGE DECK RECONSTRUCTION DETOUR PLANS
19	MAINTENANCE OF TRAFFIC I-57 AND 112TH PLACE
20	EROSION CONTROL AND LANDSCAPING PLANS
21	DRAINAGE PLANS
22	112TH PL AND MARSHFIELD AVE INTERSECTION GRADING PLAN
23	112TH PL AND HAMLET AVE INTERSECTION GRADING PLAN
24	112TH PL AND MARSHFIELD AVE ADA SIDEWALK DETAILS
25	112TH PL AND HAMLET AVE ADA SIDEWALK DETAILS
26	112TH PLACE PAVEMENT MARKING AND SIGNING PLANS
27	HAMLET AVE PAVEMENT MARKING AND SIGNING PLANS
28 - 34	LIGHTING PLANS
35 - 38	TRAFFIC SIGNAL PLANS
39 - 59	ELECTRICAL STANDARD DETAILS
60	CITY OF CHICAGO DETAIL (CC&G BV.12)
61 - 64	CITY OF CHICAGO ADA SIDEWALK DETAILS
65 - 66	BRIDGE APPROACH PAVEMENT DETAILS
67 - 88	112TH BRIDGE DECK OVER INTERSTATE 57
89	FRAMES AND LIDS ADJUSTMENT WITH MILLING; AND FRAMES AND LIDS ADJUSTMENT WITHOUT MILLING, BD08
90	CITY OF CHICAGO DRAINAGE DETAILS, BD09
91	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT, BD22
92	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT, BD24
93	BUTT JOINTS AND HMA TAPER, BD32
94	CITY OF CHICAGO CATCH BASINS, INLET AND MANHOLE DETAILS, BD47
95	ENTRANCE AND EXIT RAMP CLOSURE DETAILS, TC08
96	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS, TC10
97	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING, TC16
98	TRAFFIC CONTROL FOR SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES, TC17
99	SIGNING AND PAVEMENT MARKING TREATMENT FOR RAILROAD CROSSINGS, TC23
100- 101	CITY OF CHICAGO TYPICAL PAVEMENT MARKINGS, TC24

HIGHWAY STANDARDS

STD. NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
353001-04	PCC BASE COURSE WITH HMA BINDER AND SURFACE COURSES
420001-07	PAVEMENT JOINTS
421001-02	BAR REINFORCEMENT FOR CRC PAVEMENT
442201-03	CLASS C AND D PATCHES
515001-03	NAME PLATE FOR BRIDGES
664001-02	CHAIN LINK FENCE
701101-02	OFF-RD OPERATIONS, MULTILANE, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE
701301-03	LANE CLOSURE 2L, 2W, SHORT TIME OPERATIONS
701401-05	LANE CLOSURE, FREEWAY/ EXPRESSWAY
701411-05	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS >= 45 MPH
701446-01	TWO LANE CLOSURE FREEWAY/ EXPRESSWAY
701601-06	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
704001-05	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-02	SIGN PANEL ERECTION DETAILS
720011-01	METAL POST FOR SIGNS, MARKERS AND DELINEATORS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
112TH PLACE OVER
F.A.I ROUTE 57 (INTERSTATE 57)

INDEX OF SHEETS & HIGHWAY STANDARDS

SCALE:
DRAWN BY:
DATE: 01/16/09
CHECKED BY:

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TTBOOMWA.DGN
1-16-2009, 13:56:09
T:\DOCUMENT\93086O\CIVIL\DGN\DX005V9.DGN
HECHTBR
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63