F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1920.1B-R	COOK	101	006
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT			
CONTRACT NO. 62533				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	100% FED. URBAN X771-2A	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
				CONSTRUCTION TYPE CODE											
44003100	MEDIAN REMOVAL	SQ FT	400		400										
44200104	PAVEMENT PATCHING, TYPE I, 9 INCH	SQ YD	100		100										
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	150		150										
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SQ YD	200		200										
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	200		200										
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2460		2460										
50102400	CONCRETE REMOVAL	CU YD	64.1			64.1									
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1			1									
50157300	PROTECTIVE SHIELD	SQ YD	1613			1613									
50200100	STRUCTURE EXCAVATION	CU YD	201			201									
50300225	CONCRETE STRUCTURES	CU YD	62.6			62.6									
50300255	CONCRETE SUPERSTRUCTURE	CU YD	512.9			512.9									
50300260	BRIDGE DECK GROOVING	SQ YD	1596			1596									
50300300	PROTECTIVE COAT	SQ YD	2104			2104									
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	8210			8210									
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28			28									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120540			120540									
50800515	BAR SPLICERS	EACH	134			134									
50901730	BRIDGE FENCE RAILING	FOOT	516			516									
51500100	NAME PLATES	EACH	2			2									
52000110	PREFORMED JOINT STRIP SEAL	FOOT	171			171									
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28			28									
52100520	ANCHOR BOLTS, 1"	EACH	112			112									
58700300	CONCRETE SEALER	SQ FT	346			346									
59000200	EPOXY CRACK INJECTION	FOOT	55			55									
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	23		23										
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	10		10										
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	10		10										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12										
67100100	MOBILIZATION	L SUM	1		1										
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1										

• DENOTES SPECIALTY ITEMS
☐ NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
112TH PLACE OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TTB00WMADGN...\SL0005VA.DGN...\SU0005*3.DGN
1-16-2009 10:56:07 T:\DOCUMENT\49308601\CIVIL\DGN\SU0005VC.DGN
MECHTBR
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63