F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1920.18-R	COOK	101	008
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62533				

SUMMARY OF QUANTITIES

			100% FED. URBAN X771-2A	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	12					12						
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					2						
X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	1870					1870						
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	167	167										
X0322683	CONCRETE FOUNDATION 24" DIA.	FOOT	45					45						
X0322684	CONCRETE FOUNDATION 30" DIA.	FOOT	11					11						
X0322701	SERVICE INSTALLATION, 100 AMP	EACH	1				1							
X0322712	STREET NAME SIGN	EACH	7					7						
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	7		7									
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	8			8								
* X0324182	ELECTRICAL CABLE IN CONDUIT, TRIPLEX NO. 6, 2-1C AND NO.8, 1-1C	FOOT	3500				3500							
* X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1				1							
* X0324900	SERVICE CONNECTION TO CECO LINE	EACH	1				1							
* X0324902	REMOVE EXISTING TRAFFIC SIGNAL FOUNDATION	EACH	4					4						
* X0324917	REMOVAL OF EXISTING UNDERPASS FIXTURE, SALVAGE	EACH	12			12								
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1566		1566									
81200830	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	550				550							
X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1				1							
X0933700	PVC CONDUIT IN TRENCH, 2" (SCHEDULE #80)	FOOT	1710				1710							
X0933900	PVC CONDUIT IN TRENCH, 3" (SCHEDULE #80)	FOOT	84					84						
X0934000	PVC CONDUIT IN TRENCH 4" (SCHEDULE #80)	FOOT	151					151						
X0934200	JUNCTION BOX AND TERMINAL ATTACHED TO POLE OR POST	EACH	12					12						
X0934500	FIBER OPTIC SIGN, BRACKET MOUNTED	EACH	9					9						
* X0934800	MAST ARM, STEEL, MONOTUBE, 20 FT.	EACH	2					2						
X0934900	MAST ARM, STEEL, MONOTUBE, 26 FT.	EACH	3					3						
X0935100	MAST ARM, STEEL, MONOTUBE 35 FT.	EACH	1					1						
X0935700	ELECTRIC CABLE IN CONDUIT NO. 12 19/C	FOOT	1358					1358						
X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1					1						
X0966520	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, BRACKET MOUNTED	EACH	9				9							
X0966700	JUNCTION BOX, POLE OR POST MOUNTED	EACH	13					13						
X0301074	DRILL EXISTING MANHOLE	EACH	14					14						

* DENOTES SPECIALTY ITEMS
□ NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
112TH PLACE OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

...\TBOOMRA.DGN ...\SUMQOSYA.DGN ...\SUMQOS~1.DGN
H:6-2009.INS6dl T:\DOCUMENT\93086\CIVIL\DGN\SUMQOT~1.DGN
HECHTER