

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE ①	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE												
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1																	
<del>8160820</del>	<del>CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL (1 VC COATED)</del>	<del>FOOT</del>	<del>620</del>																		
* X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1				1														
* X0323157	REMOVE LUMINAIRE FROM UNDERPASS	EACH	12			12															
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	375	375																	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	36	36																	
Z0018800	DRAINAGE SYSTEM	L SUM	1		1																
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	55				40	15													
Z0030240	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2																	
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4																	
Z0064800	SELECTIVE CLEARING	UNIT	1	1																	
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		1																
Z0076600	TRAINEES	Hour	1,000	1,000																	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1																	
<del>81101000</del>	<del>CALVANIZED STEEL CONDUIT ATTACHED TO STRUCTURE, 4" DIA., LIGHT</del>	<del>FOOT</del>	<del>230</del>																		
* X0326360	POLE, STEEL, 10" DIAMETER, 3 GAUGE, 32'-6" HEIGHT	EACH	2					2													
* B1900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	1861				1710	151													
* B1200230	(PVC) CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., LIGHTING FOUNDATION REMOVAL	FOOT	510				510														
* B4200700	LIGHTING FOUNDATION REMOVAL	EACH	12				12														
* X0326349	ELECTRIC CABLE IN CONDUIT NO. 1 1/C	FOOT	800				800														
* X0326361	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE, 7 FOOT	EACH	1				1														
* B1702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	265				265														
* X8250085	LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE	EACH	1				1														
* X8300100	LIGHT POLE, ALUMINUM, WITH MAST ARM, INSTALL ONLY	EACH	20				20														
* B2107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12			12															
* X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1			1															
* B1028030	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 1"	FOOT	1276					1276													
* X0326347	ELECTRIC CABLE IN CONDUIT NO. 4 2 C	FOOT	130					130													
* B7301155	ELECTRIC CABLE IN CONDUIT, NO. 12 7 C	FOOT	520					520													
* X8210407	LUMINAIRE, INSTALL ONLY	EACH	20				20														

\* DENOTES SPECIALTY ITEMS  
 □ NON-PARTICIPATING  
 @ Y080

### BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57      S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 112TH PLACE OVER  
 F.A.I. ROUTE 57 (INTERSTATE 57)

### SUMMARY OF QUANTITIES

SCALE: N.T.S.      DRAWN BY: BRH  
 DATE: 01/16/09      CHECKED BY: ACL

**TENG**  
TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 205 N. MICHIGAN AVE. CHICAGO, IL 60601  
 TELEPHONE: 312/618-0000

H:\PROJECTS\112TH PL. OVER NB & SB I-57\112TH PL. OVER NB & SB I-57\SUMMARY OF QUANTITIES.DWG  
 1/16/09 10:56:03  
 1 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100